

# RECORD COPY PCT

## REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For receiving Office use only

PCT/US 014489

International Application No.

25 MAY 2000

(25.05.00)

International Filing Date

PCT INTERNATIONAL  
APPLICATION RO/US

Name of receiving Office and PCT International Application No.

Applicant's or agent's file reference  
(if desired) (12 characters maximum) 11613.33WO01

### Box No. I TITLE OF INVENTION

CDK4 BINDING PEPTIDE

### Box No. II APPLICANT

Name and address (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

PATERSON, Bruce M.  
9806 Holmhurst Road  
Bethesda, Maryland 20817  
United States of America

☒ This person is also inventor

Telephone No.

Facsimile No.

Teleprinter No.

State (that is, country) of nationality:  
US

State (that is, country) of residence:  
US

This person is applicant for the purposes of: ☒ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

### Box No. III FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)

Name and address (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)

ZHANG, Jian-Min  
900 Pump Road #4  
Richmond, Virginia 23233  
United States of America

This person is:

☐ applicant only

☒ applicant and inventor

☐ inventor only (If this check-box is marked, do not fill in below.)

State (that is, country) of nationality:  
CN

State (that is, country) of residence:  
US

This person is applicant for the purposes of: ☒ all designated States ☐ all designated States except the United States of America ☐ the United States of America only ☐ the States indicated in the Supplemental Box

☐ Further applicants and/or (further) inventors are indicated on a continuation sheet.

### Box No. IV AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE

The person identified below is hereby has been appointed to act on behalf of the applicant(s) before the competent International Authorities as ☒ agent ☐ common representative

Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)

DAIGNAULT, Ronald A.  
MERCHANT & GOULD P.C.  
P.O. Box 2903  
Minneapolis, Minnesota 55402-0903  
United States of America

Telephone No.  
612-371-5381

Facsimile No.  
612-336-4751

Teleprinter No.

☐ Mark this check-box where no agent or common representative is has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.

**Box No. V DESIGNATION OF STATES**

The following designations are hereby made under Rule 4.9(a) (mark the applicable check-boxes; at least one must be marked):

**Regional Patent**

- ☐ **AP ARIPO Patent:** GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ Tanzania, UG Uganda, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT
- ☐ **EA Eurasian Patent:** AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☐ **EP European Patent:** AT Austria, BE Belgium, CH and LI Switzerland and Liechtenstein, CY Cyprus, DE Germany, DK Denmark, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ **OA OAPI Patent:** BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

**National Patent** (if other kind of protection or treatment desired, specify on dotted line):

- |   |   |
|---|---|
| <input type="checkbox"/> AE United Arab Emirates                  | <input type="checkbox"/> KZ Kazakstan                                 |
| <input type="checkbox"/> AG Antigua and Barbuda                   | <input type="checkbox"/> LC Saint Lucia                               |
| <input type="checkbox"/> AL Albania                               | <input type="checkbox"/> LK Sri Lanka                                 |
| <input type="checkbox"/> AM Armenia                               | <input type="checkbox"/> LR Liberia                                   |
| <input type="checkbox"/> AT Austria and utility model             | <input type="checkbox"/> LS Lesotho                                   |
| <input type="checkbox"/> AU Australia                             | <input type="checkbox"/> LT Lithuania                                 |
| <input type="checkbox"/> AZ Azerbaijan                            | <input type="checkbox"/> LU Luxembourg                                |
| <input type="checkbox"/> BA Bosnia and Herzegovina                | <input type="checkbox"/> LV Latvia                                    |
| <input type="checkbox"/> BB Barbados                              | <input type="checkbox"/> MA Morocco                                   |
| <input type="checkbox"/> BG Bulgaria                              | <input type="checkbox"/> MD Republic of Moldova                       |
| <input type="checkbox"/> BR Brazil                                | <input type="checkbox"/> MG Madagascar                                |
| <input type="checkbox"/> BY Belarus                               | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia |
| <input type="checkbox"/> CA Canada                                | <input type="checkbox"/> MN Mongolia                                  |
| <input type="checkbox"/> CH and LI Switzerland and Liechtenstein  | <input type="checkbox"/> MW Malawi                                    |
| <input type="checkbox"/> CN China                                 | <input type="checkbox"/> MX Mexico                                    |
| <input type="checkbox"/> CR Costa Rica                            | <input type="checkbox"/> MZ Mozambique                                |
| <input type="checkbox"/> CU Cuba                                  | <input type="checkbox"/> NO Norway                                    |
| <input type="checkbox"/> CZ Czech Republic and utility model      | <input type="checkbox"/> NZ New Zealand                               |
| <input type="checkbox"/> DE Germany and utility model             | <input type="checkbox"/> PL Poland                                    |
| <input type="checkbox"/> DK Denmark and utility model             | <input type="checkbox"/> PT Portugal                                  |
| <input type="checkbox"/> DM Dominica                              | <input type="checkbox"/> RO Romania                                   |
| <input type="checkbox"/> DZ Algeria                               | <input type="checkbox"/> RU Russian Federation                        |
| <input type="checkbox"/> EE Estonia and utility model             | <input type="checkbox"/> SD Sudan                                     |
| <input type="checkbox"/> ES Spain                                 | <input type="checkbox"/> SE Sweden                                    |
| <input type="checkbox"/> FI Finland and utility model             | <input type="checkbox"/> SG Singapore                                 |
| <input type="checkbox"/> GB United Kingdom                        | <input type="checkbox"/> SI Slovenia                                  |
| <input type="checkbox"/> GD Grenada                               | <input type="checkbox"/> SK Slovakia and utility model                |
| <input type="checkbox"/> GE Georgia                               | <input type="checkbox"/> SL Sierra Leone                              |
| <input type="checkbox"/> GH Ghana                                 | <input type="checkbox"/> TJ Tajikistan                                |
| <input type="checkbox"/> GM Gambia                                | <input type="checkbox"/> TZ Tanzania                                  |
| <input type="checkbox"/> HR Croatia                               | <input type="checkbox"/> TM Turkmenistan                              |
| <input type="checkbox"/> HU Hungary                               | <input type="checkbox"/> TR Turkey                                    |
| <input type="checkbox"/> IN India                                 | <input type="checkbox"/> TT Trinidad and Tobago                       |
| <input type="checkbox"/> ID Indonesia                             | <input type="checkbox"/> UA Ukraine                                   |
| <input type="checkbox"/> IL Israel                                | <input type="checkbox"/> UG Uganda                                    |
| <input type="checkbox"/> IS Iceland                               | <input checked="" type="checkbox"/> US United States of America       |
| <input type="checkbox"/> JP Japan                                 | <input type="checkbox"/> UZ Uzbekistan                                |
| <input type="checkbox"/> KE Kenya                                 | <input type="checkbox"/> VN Viet Nam                                  |
| <input type="checkbox"/> KG Kyrgyzstan                            | <input type="checkbox"/> YU Yugoslavia                                |
| <input type="checkbox"/> KP Democratic People's Republic of Korea | <input type="checkbox"/> ZA South Africa                              |
| <input type="checkbox"/> KR Republic of Korea and utility model   | <input type="checkbox"/> ZW Zimbabwe                                  |

In addition to the designations made above, the applicant also makes under Rule 4.9(b) all designations which would be permitted under the PCT except the designation(s) of \_\_\_\_\_

The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation of a designation consists of the filing of a notice specifying that designation and the payment of the designation and confirmation fees. Confirmation must reach the receiving Office within the 15-month time limit.)

<b>Box No. VI PRIORITY CLAIM</b>		<input type="checkbox"/> Further priority claims are indicated in the Supplemental Box.		
Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country	regional application:* regional Office	international application: receiving Office
item (1) 18 June 1999 (18.06.1999)	60/139,934	US		
item (2)				
item (3)				

☒ The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of the present international application is the receiving Office) identified above as item(s): (1)

\* Where the earlier application is an ARIPO application, it is mandatory to indicate in the Supplemental Box at least one country party to the Paris Convention for the Protection of Industrial Property for which the earlier application was filed (Rule 4.10(b)(ii)). See Supplemental Box.

<b>Box No. VII INTERNATIONAL SEARCHING AUTHORITY</b>		
<b>Choice of International Searching Authority (ISA)</b> (If two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used): ISA / EP	<b>Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):</b> Date (day/month/year):      Number:      Country (or regional Office):	

<b>Box No. VIII CHECK LIST: LANGUAGE OF FILING</b>	
This international application contains the following number of sheets: request : 4 description (excluding sequence listing part) : 39 claims : 2 abstract : 1 drawings : 14 sequence listing part of description : 0 <b>Total number of sheets : 60</b>	This international application is <b>accompanied by</b> the item(s) marked below: 1. <input checked="" type="checkbox"/> fee calculation sheet 2. <input type="checkbox"/> separate signed power of attorney 3. <input type="checkbox"/> copy of general power of attorney; reference number, if any: 4. <input type="checkbox"/> statement explaining lack of signature 5. <input type="checkbox"/> priority document(s) identified in Box No VI as item(s): 6. <input type="checkbox"/> translation of international application into (language): 7. <input type="checkbox"/> separate indications concerning deposited microorganism or other biological material 8. <input type="checkbox"/> nucleotide and/or amino acid sequence listing in computer readable form 9. <input checked="" type="checkbox"/> Other (specify): Gen. Transmittal (in dupl) Check in the amount of \$ 2064. Return Postcard
<b>Figure of the drawings</b> which should accompany the abstract:	<b>Language of filing</b> of the international application: English

<b>Box No. IX SIGNATURE OF APPLICANT OR AGENT</b>	
Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).	
By <u>Ronald A. Daignault</u>	(25.05.00)

For receiving Office use only		2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
1. Date of actual receipt of the purported international application:	40 Rec'd PCT/PTO 25 MAY 2000	
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA/EP	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid	

For International Bureau use only	
Date of receipt of the record copy by the International Bureau:	26 JUNE 2000 (26.06.00)

**CDK4 BINDING PEPTIDE****BACKGROUND OF THE INVENTION**

The division cycle of eukaryotic cells is regulated by a family of protein  
5 kinases known as cyclin-dependent kinases (CDKs). The sequential activation of  
individual members of this family and their consequent phosphorylation of critical  
substrates promotes orderly progression through the cell cycle. CDK activities are  
regulated by cyclin binding, by both positive and negative regulatory  
phosphorylations and by polypeptide CDK inhibitors. Cellular differentiation is  
10 accompanied by the down-regulation of CDK activity, which occurs through at least  
two mechanisms: down-regulation of cyclin expression which is required for CDK  
activity; and induction of CDK inhibitor expression. CDK4 is a major catalytic  
subunit of mammalian D-type cyclins, which act during the G<sub>1</sub> phase of the cell  
cycle to enforce the decision of cells to enter the S phase. The deregulation of  
15 eukaryotic CDKs is correlated with many types of cancers.

Three D-type cyclins (D1, D2 and D3) are differentially expressed in  
proliferating cells in response to various growth factor mediated signals. The D-  
type cyclins interact combinatorially with CDKs 2, 4, 5 and 6 to form active  
holoenzymes that facilitate progression through the G<sub>1</sub> phase of the cell cycle into S  
20 phase. Expression of the D-type cyclins depends on mitogenic stimulation,  
regardless of the position of the cell in the cycle. Growth factor withdrawal leads to  
rapid cyclin D destruction, with an associated loss of CDK activity.

A classical example of terminal differentiation is that of skeletal muscle  
cells. Skeletal muscle differentiation entails the coordination of muscle specific  
25 gene expression and terminal withdrawal from the cell cycle. Muscle differentiation  
is intimately coupled to the cell cycle, such that muscle-specific transcription is  
initiated only when myoblasts are growth arrested in the G<sub>1</sub>/G<sub>0</sub> phase.

MyoD is a basic helix-loop-helix (bHLH) protein which plays an important  
role in the differentiation of skeletal muscle by inducing muscle structural gene  
30 expression and cell cycle withdrawal. In particular, MyoD is one of several  
transcriptional activators of muscle specific gene expression. The mechanisms by  
which MyoD induces myogenesis involve both the activation of muscle-specific  
gene expression and withdrawal from the cell cycle. Although proliferating  
myoblasts express MyoD throughout the cell cycle, the functions of MyoD are  
35 repressed in proliferating myoblasts.

Tumor suppressor retinoblastoma protein (RB) suppresses cell proliferation and thus plays an important role in the production and maintenance of the terminally differentiated phenotype of muscle cells. RB also appears to participate in control of entry into the S phase of the cell cycle. Inactivation of RB in terminally differentiated cells allows the cells to reenter the cell cycle. Correspondingly, loss of a functional RB is key step in the development of many human tumors.

The activity of RB is modulated by a phosphorylation/dephosphorylation mechanism during cell proliferation and differentiation. In resting or differentiated cells, RB protein is present in its dephosphorylated form. Underphosphorylated RB inhibits growth promoting transcription factors in the E2F / DP family. In rapidly proliferating cells, RB protein is highly phosphorylated. Maximal phosphorylation is associated with S phase of the cell cycle. Cyclins and CDKs contribute to the sequential phosphorylation of RB to inactivate its growth suppressive function.

#### SUMMARY OF THE INVENTION

The inventors have identified a peptide (hereinafter referred to as a "CDK4 binding peptide") that is capable of specifically binding a cyclin dependent kinase (CDK4) to inhibit CDK4 activity and cell growth. In one embodiment, the invention provides an isolated nucleic acid sequence comprising DNA encoding the CDK4 binding peptide or a nucleic acid sequence that is complementary to the isolated nucleic acid sequence and remains stably bound to it under at least moderate, and optionally, under high stringency conditions.

In another embodiment, the invention provides an isolated CDK4 binding peptide [SEQ. ID NO: 1]. The invention also includes variants of the CDK4 binding peptide which comprise polypeptides which have at least about 80% amino acid sequence identity with the amino acid sequence of the CDK4 binding peptide.

In another embodiment, the invention provides chimeric molecules comprising a CDK4 binding peptide fused to a heterologous peptide or amino acid sequence, preferably a nuclear localization signal.

Therapeutic and diagnostic methods are also provided.

#### BRIEF DESCRIPTION OF THE FIGURES

**Figure 1** is a photograph of a gel showing that MyoD binding to CDK4 does not depend upon cyclin D1.

**Figure 2** is a graph showing the in vivo interaction between MyoD and CDK4 in the mammalian two-hybrid system.

**Figure 3** is a gel showing the interaction of MyoD and CDK4 in dividing C2C12 myoblasts.

5        **Figure 4** is a photograph of a gel showing that CDK4 specifically inhibits MyoD-E12 DNA-binding in the absence of cyclin D1.

**Figure 5** is a graph showing that CDK4 differentially inhibits MyoD and myogenin activation of the MCK CAT reporter plasmid in 10T1/2 cells grown in differentiation medium (DM).

10       **Figure 6** is a graph showing forced nuclear expression of CDK4 inhibits myogenic conversion of 10T1/2 cells in differentiation medium (DM) in the absence of cyclin D1.

**Figure 7** is a photograph of a gel showing that MyoD and RB are not phosphorylated comparably by CDK4 in vitro.

15       **Figure 8a** is a graph showing that gal 4-RB and vp16-E2F interact to activate luciferase expression 10–15 fold routinely, whereas vp16-MyoD and vp16-myogenin show no significant activation above background with gal4-RB.

**Figure 8b** is a graph showing that both vp16-MyoD and vp16-myogenin interact strongly with gal4-E12.

20       **Figure 9** is a schematic characterization of the CDK-binding domain in MyoD(CMD1) and regions used to study MyoD-CDK4 interactions.

**Figure 10a** is a photograph of a gel showing that CDK4 binds to the carboxy terminus of MyoD (lane 5) but does not bind to the other vertebrate myogenic factors; GST myogenin shown as an example (lane 3).

25       **Figure 10b** is a photograph of a gel showing that a fifteen amino acid domain between amino acid residues 189–203 that is required for CDK4 binding (lanes 4 and 5).       **Figure 10c** is a photograph of a gel showing that the fifteen amino acid CDK4-binding domain in MyoD (aa 189–203) binds CDK4 as efficiently as full-sized MyoD when joined to GST (lanes 2 and 3).

30       **Figure 11a** is a photograph of a gel showing that extracts from Sf9 cells coinfecting with wild type virus (lane 1), a cyclin D1 encoding virus (lane 2) or a CDK4 encoding virus (lane 3) give background levels of kinase activity on serine 780 (antibody to phosphoserine 780) whereas coinfections with baculovirus stock encoding CDK4 and cyclin D1 produce active CDK4 (lane 4) that specifically  
35       phosphorylates RB (GST RB (aa 767–928)) on serine 780. This phosphorylation is

inhibited to background levels by the CDK specific kinase inhibitor p16 (lane 5, added as GST-p16).

**Figure 11b** is a photograph of a gel showing that full sized MyoD(CMD1) (second row), the C-terminus of MyoD(CMD1) (third row) and the fifteen amino acid CDK4 binding domain of MyoD fused to GST (fourth row) inhibit the CDK4-dependent phosphorylation of RB(GST-RB) in vitro whereas myogenin (first row) has no inhibitory affect).

**Figure 12** is a table showing the growth inhibitory effects of the various MyoD(CMD1) subdomains joined to either the pCDNA3 or GST-pCEFL vectors. The number of BrdU positive cells per 500 lacZ positive cells, normalized to vector and averaged for six independent assays is shown. In the top panel, constructs were expressed with the pCDNA3 vector. In the lower panel constructs were fused to eukaryotic expression vector, GST-pCEFL, and contained a nuclear localization signal.

**Figure 13** is a photograph of a gel showing the inhibition of RB phosphorylation in C2C12 myoblasts by MyoD(CMD1) and the C-terminus containing the fifteen amino acid CDK4 binding peptide.

**Figure 14** is a sequence comparison of the fifteen amino acid CDK4 binding peptide in chicken MyoD(CMD1) versus human, rat, mouse, pig, xenopus and zebra fish. The consensus is given between chicken and mammals.

## **DETAILED DESCRIPTION**

### **Definitions**

The term "CDK4 binding peptide", when used herein, encompasses both the native sequence shown and variants thereof (which are further defined herein). The CDK4 binding peptide may be isolated from a variety of sources, such as vertebrate sources, including human tissue types, or from another source, or prepared by recombinant or synthetic methods.

A "native" CDK4 binding peptide sequence comprises a polypeptide having the same amino acid sequence as a CDK4 binding peptide derived from nature. Native sequences can be isolated from nature or can be produced by recombinant or synthetic means.

A "variant" of the CDK4 binding peptide includes peptide sequences having at least about 80% amino acid sequence identity with the CDK4 binding peptide

shown in [SEQ. ID NO: 1], more preferably about 90%, even more preferably about 95% sequence identity.

"Percent (%) amino acid sequence identity" with respect to the CDK4 binding peptide sequence is defined as the percentage of amino acid residues in a candidate sequence that are identical to the amino acid residues in the CDK4 binding peptide sequence, after aligning the sequences and introducing gaps, if necessary to introduce maximum percent sequence identity, and not considering any conservative substitutions as part of the sequence identity. Alignment for purposes of determining percent amino acid sequence identity can be achieved in various ways that are within the skill in the art, for instance, using publicly available computer software such as BLAST, ALIGN or Megalign (DNASTAR) software. Those skilled in the art can determine appropriate parameters for measuring alignment, including any algorithms needed to achieve maximal alignment over the full length of the sequences being compared.

"Percent (%) nucleic acid sequence identity" with respect to the nucleic acid sequences encoding the CDK4 binding peptide is defined as the percentage of nucleotides in a candidate sequence that are identical to the nucleotides in the nucleic acid sequence encoding the CDK4 binding peptide after aligning the sequences and introducing gaps, if necessary, to achieve the maximum percent sequence identity. Alignment for the purpose of determining percent nucleic acid sequence identity can be achieved in various ways that are within the skill in the art, for instance, using publicly available computer software such as BLAST, ALIGN, or Megalign (DNASTAR) software. Those skilled in the art can determine appropriate parameters for measuring alignment, including any algorithms needed to achieve maximal alignment over the full length of the sequences being compared.

"Isolated" when used to describe the peptides disclosed herein, means a polypeptide that has been identified and separated and/or recovered from a component of its natural environment. Contaminant components of its natural environment are materials that would typically interfere with diagnostic or therapeutic use of the polypeptide, and may include enzymes, hormones, and other proteinaceous or non-proteinaceous solutes. In preferred embodiments, the polypeptide is purified (1) to a degree sufficient to obtain at least 15 residues of N-terminal or internal amino acid sequence by use of a spinning cup sequenator, or (2) to homogeneity by SDS-PAGE under non-reducing or reducing conditions using Coomassie blue or, preferably, silver stain. Isolated polypeptide includes



polypeptide *in situ* within recombinant cells, since at least one component of the CDK4 binding peptide natural environment will not be present. Ordinarily, however, isolated polypeptide is prepared by at least one purification step.

5 An "isolated" nucleic acid molecule is a nucleic acid molecule that is identified and separated from at least one contaminant nucleic acid molecule with which it is ordinarily associated. An isolated nucleic acid molecule is other than in the form or setting in which it is found in nature. However, an isolated nucleic acid molecule includes nucleic acid molecules contains in cells that ordinarily express the protein encoded by that nucleic acid molecule where, for example, the nucleic acid  
10 molecule is in a chromosomal location different from that found in nature.

The term "control sequence" refers to DNA sequences necessary for the expression of an operably linked coding sequence in a particular host organism. The control sequences that are suitable for prokaryotes, for example, include a promoter, optionally an operator sequence, and a ribosome binding site. Eukaryotic cells are  
15 known to utilize promoters, polyadenylation signals, and enhancers.

Nucleic acid is "operably linked" when it is placed into a functional relationship with another nucleic acid sequence. For example, DNA for a Nuclear Localization Signal is operably linked to DNA encoding the CDK4 binding peptide if the expressed protein is localized in the nucleus thereby; a promoter or enhancer is  
20 operably linked to a coding sequence if it affects the transcription of the sequence. Generally, "operably linked" means that the DNA sequences being linked are contiguous, preferably in the same reading frame. However, enhancers do not have to be contiguous. Linking is accomplished by ligation at convenient restriction sites. If such sites do not exist, a synthetic oligonucleotide adaptor or linkers can be used  
25 in accordance with conventional practice.

The term "antibody" is used in the broadest sense and specifically covers single anti-CDK4 binding peptide monoclonal antibodies (including agonist, antagonist, and neutralizing or blocking antibodies) and antibody compositions with polypepitopic specificity. The term "monoclonal antibody" as used herein refers to an  
30 antibody obtained from a population of substantially homogeneous antibodies, i.e., the individual antibodies comprising the population are identical except for possible naturally occurring mutations that may be present in minor amounts.

"Active" or "activity" for the purposes herein refers to form(s) of the CDK4 binding peptide which retain the biologic activities of native or naturally occurring  
35 MyoD having a CDK4 binding domain.

The terms "cancer" and "cancerous" refer to or describe the physiological condition in mammals that is typically characterized by unregulated cell growth. Examples of cancer include but are not limited to, carcinoma, lymphoma, blastoma, sarcoma, and leukemia. Particular examples of cancer include osteosarcoma and rhabdomyosarcoma.

The terms "treating", "treatment", and "therapy" as used herein refer to curative therapy, prophylactic therapy and preventative therapy.

Amino acids may be classified according to the polarities of their side chains. An amino acid having a "non-polar side chain" refers to an amino acid having a side chain that is generally hydrophobic and tends to cluster with other hydrophobic molecules when placed in an aqueous environment, such as water. Examples of amino acids having non-polar side chains are glycine, alanine, valine, leucine, isoleucine, methionine, proline, phenylalanine, and tryptophan. An amino acid having an "uncharged polar side chain" refers to an amino acid having a side chain which includes a hydroxyl, amide or thiol group. Examples of amino acids with uncharged polar side chains are serine, threonine, asparagine, glutamine, tyrosine and cysteine. An amino acid having a "charged polar side chain" refers to an amino acid having a side chain that is generally hydrophilic. Examples of amino acids having charged polar side chains include lysine, arginine, histidine, aspartic acid and glutamic acid. An amino acid having an "uncharged side chain" includes amino acids with both "non-polar side chains" and "uncharged polar side chains." An amino acid having a "polar side chain" includes amino acids with both "uncharged polar side chains" and "charged polar side chains." Other non-standard amino acids may also be classified using this system.

### Composition

The invention is directed towards a newly identified and isolated amino acid sequences and a nucleic acid sequence coding therefore. The isolated peptide of the invention is capable of specifically binding cyclin dependent kinase (CDK4), thereby inhibiting the activity of CDK4 and cell growth. The isolated peptide will hereinafter be referred to as a "CDK4 binding peptide." The CDK4 binding peptide of the invention includes the following fifteen amino acid sequence: Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub> [SEQ. ID NO: 1] wherein Xaa<sub>1</sub> is an amino acid having an uncharged polar side chain, including Cys or Ser; Xaa<sub>2</sub> is an amino acid having an uncharged side chain, including Ser or

Gly; Xaa<sub>3</sub> is an amino acid having an uncharged side chain, including Ser, Ala or Pro; Xaa<sub>4</sub> is an amino acid having a polar side chain, including Arg or Gln; Xaa<sub>5</sub> is an amino acid having an uncharged side chain, including Ser, Cys or Gly; and Xaa<sub>6</sub> is an amino acid having a charged polar side chain, including Asp or Glu. Examples  
 5 of amino acid sequences which correspond to the CDK4 binding peptide of this invention are depicted in Figure 14.

The invention is also directed towards a nucleic acid sequence encoding the CDK4 binding peptide sequence. The nucleotide sequence which encodes the 15 amino acid CDK4 binding peptide of the claimed invention can be determined from  
 10 various published nucleotide sequences for MyoD. See, Table 1. For example, (a) the complete nucleotide sequence of human MyoD can be found in GenBank at Accession Number X56677 or EMBL Accession Number AF027148 which correspond to Pearson-White, S.H., "Human MyoD: cDNA and deduced amino acid sequence" Nucleic Acids Res. 19(5): 1148 (1991) and Chen, B., et al. "Methylation  
 15 alterations of the MyoD1 upstream region are predictive of subclassification of human rhabdosarcomas" Am J. Pathol. 152(4): 1071-1079 (1998); (b) the nucleotide sequence which encodes chicken MyoD can be found in GenBank at Accession Number X16189 which corresponds to Lin et al., "An avian muscle factor related to MyoD1 activates muscle-specific promoters in nonmuscle cells of  
 20 different germ-layer origin and in BrdU-treated myoblasts," Genes Dev. 3(7):986-96 (1989); (c) the nucleotide sequence which encodes Zebrafish MyoD can be found in GenBank/EMBL at Accession Number Z36945 which corresponds to Weinberg, et al. "Development regulation of zebrafish MyoD in wild-type, no tail and spadetail embryos" Development 122:2711-280 (1996). It should be noted that the  
 25 amino acids which correspond to the CDK4 binding peptide for the various organisms provided above are not the same for each.

Applicants also recognize, and include within the scope of their invention, a nucleic acid sequence for the CDK4 binding peptide which contains codons that are modified according to optimal codon frequencies for a particular cellular host.  
 30 Redundancy in the genetic code permits variation in the gene sequence. In particular, specific codon preferences are recognized for a specific host such that the disclosed sequence can be adapted as preferred for the desired host. For example, rare codons having a frequency of less than about 20% in known sequences of the desired host are preferably replaced with higher frequency codons. A standard

textbook on cell biology such as Genes V, Benjamin Lewin ed. Oxford University Press (1994) (see, Chapter 7, page 172, Fig. 7.9) can be consulted for information on the degeneracy of the genetic code and to provide information regarding the various nucleic acid codons and to which amino acid they correspond.

5 **Table 1.**

Source/Species	GenBank/EMBL Accession No.	Journal
Chicken	L34006	Dechesne, C.A., et al. "E-box and MEF-2 independent muscle-specific expression, positive autoregulation, and cross-activation of the chicken MyoD (CMD1) promoter reveal an indirect regulatory pathway" <i>Mol. Cell. Biol.</i> 14(8): 5474-86 (1994)
Human	X5667; AF027148 (EMBL)	Pearson-White, S.H., "Human MyoD: cDNA and deduced amino acid sequence" <i>Nucleic Acids Res.</i> 19(5): 1148 (1991); Chen, B., et al. "Methylation alterations of the MyoD1 upstream region are predictive of subclassification of human rhabdosarcomas" <i>Am J. Pathol.</i> 152(4): 1071-1079 (1998).
Rat	M84176 (EMBL)	Vaida, T.B., et al. "Isolation and structural analysis of the Rat MyoD gene" <i>Gene</i> 116: 223-230 (1992)
Murine	M18779; M84918;	Davis, R.L., et al "Expression of a single transfected cDNA converts fibroblasts to myoblasts" <i>Cell</i> 51: 987-1000 (1987); Pinney, D.F., et al. "Myogenic lineage determination and differentiation: Evidence for a regulatory gene pathway" <i>Cell</i> 53: 781-93 (1988)
Pig	U12574	Chang, K.C., et al. "Cloning and in vivo expression of the pig MyoD gene" <i>J. Muscle Res. Cell. Motil.</i> 16(3): 243-47 (1995).
Xenopus-A	X16106/M31116	Hopwood, N.D., et al. "MyoD expression in the forming somites is an early response to mesoderm induction in <i>Xenopus</i> embryos" <i>EMBO J.</i> 8(11): 3409-17 (1989); Scales, J.B., et al. "Two distinct <i>Xenopus</i> genes with homology to MyoD1 are expressed before somite formation in early embryogenesis" <i>Mol. Cell. Biol.</i> 10: 1516-1524 (1990); and
Zebrafish	Z36945	Weinberg, et al. "Developmental regulation of zebrafish MyoD in wild-type, no tail and spadetail embryos" <i>Development</i> 122: 2711-280 (1996).

The peptide of the invention is an amino acid domain from the carboxyterminal region of muscle specific transcription factor (MyoD) which includes the CDK4 binding domain. The CDK4 binding peptide sequence of the invention is well conserved among MyoD proteins of the higher vertebrates (Figure 14). While not wishing to be bound by theory, the inventors believe that the peptide sequence of the invention specifically binds to CDK4 to inhibit kinase activity. In particular, the inventors believe that interaction inhibits the kinase activity of CDK4 towards retinoblastoma protein (RB). This interaction provides an alternative mechanism that allows MyoD to restrict cell differentiation, independent of a direct interaction with the retinoblastoma protein.

Unlike other vertebrate myogenic factors, the interaction between the peptide of the invention and CDK4 does not involve a highly conserved bHLH domain. Helix-Loop-Helix (HLH) is a motif that is found in a large family of nuclear proteins which appear to play a fundamental role in cellular growth, transcription, and differentiation. The structure, function and location of the bHLH domain is known to those of skill in the art and is published by Ma et al, Cell, 77: 451-459; (1994). Additionally, Figure 9 provides the amino acid locations of the various domains of chicken MyoD.

In contrast to previous studies that only correlate the bHLH domain of MyoD with growth arrest (Crescenzi et al., PNAS USA, 1990, 87(21):8442-6; and Sorrentino et al., Nature, 1990 345(6278):813-5), the inventors have found that the amino terminus of MyoD exhibits no growth arrest properties, whereas the bHLH domain, and to a greater extent, the carboxy terminus of MyoD both inhibit cell growth. In fact, the inventors have found that the CDK4 binding peptide alone is sufficient to inhibit cell growth and is actually the most efficient growth inhibitory domain in MyoD.

#### Nuclear Localization Signal

The inventors have also discovered that cyclin D1 regulates MyoD function and the onset of myogenesis by controlling the cellular location of CDK4. In the presence of cyclin D1, CDK4 is translocated from the cytoplasm to nucleus. If it is in sufficient excess to MyoD, nuclear CDK4 sequesters nuclear MyoD and thus inhibits activation of muscle specific genes.

Correspondingly, the inventors have found that the growth inhibitory effect of the CDK4 binding peptide of the invention is enhanced when the peptide further includes nuclear localization signal (NLS) (data not shown). The NLS can be placed anywhere in the protein. For example, the NLS signal can be attached at the amino terminus of the fifteen amino acid MyoD CDK4 binding peptide and fused to GFP. Suitable NLS are described by Fischer-Fantuzzi, et al., *Mol. Cell. Biol.*; 8: 5494-5503 (1988).

#### Amino Acid Variants

Covalent modifications of the CDK4 binding peptide are included within the scope of this invention. One type of modification includes deamidation of glutaminyl and asparaginyl residues to the corresponding glutamyl and aspartyl residues, respectively, hydroxylation of proline and lysine, phosphorylation of hydroxyl groups of seryl or threonyl residues, methylation of the  $\alpha$ -amino groups of lysine, arginine and histidine side chains, acetylation of the N-terminal amine, and amidation of any C-terminal carboxyl groups. Another covalent modification includes altering the native glycosylation pattern of the polypeptide, for example, by deleting one or more carbohydrate moieties found in the native CDK4 binding peptide and/or adding one or more glycosylation sites that are not present in the native sequence. Another type of covalent modification includes linking the CDK4 binding peptide to one of a variety of non-proteinaceous polymers, e.g., polyethylene glycol, polypropylene glycol, or polyoxyalkylenes.

The CDK4 binding peptide of the invention may also be modified to form a chimeric molecule which includes the CDK4 binding peptide fused to another, heterologous peptide or amino acid sequence. The inventors have found that such fusion proteins can induce growth arrest as efficiently as full-sized MyoD. In one embodiment, the chimeric molecule includes the CDK4 binding peptide fused to a nuclear localization signal. Other examples of heterologous peptide or amino acid sequences include peptides which target the molecule to specific cells, for example, by attachment to an antibody against a surface protein of the target cell. Additionally, the protein can be targeted to various compartments of the cell including the nucleus, the mitochondria (Rizutto et al. *Nature*; 358: 325-327 (1992)), and endoplasmic reticulum (Munro et al. *Cell*; 48: 899-907 (1987)).

### Nucleic Acid Variants

Applicants recognize, and include within the scope of their invention, a nucleotide sequence (DNA or RNA) encoding the peptide sequence which contains codons that are modified according to optimal codon frequencies for a particular  
5 cellular host.

Redundancy in the genetic code permits variation in the gene sequence encoding the peptide sequence of the invention. In particular, specific codon preferences are recognized for a specific host such that the disclosed sequence can be adapted as preferred for the desired host. For example, rare codons having a  
10 frequency of less than about 20% in known sequences of the desired host are preferably replaced with higher frequency codons.

### Preparation of CDK4 Binding Peptide

The description below relates primarily to production of CDK4 binding  
15 peptide by culturing cells transformed or transfected with a vector containing CDK4 nucleic acid. It is, of course, contemplated that alternative methods, which are well known in the art, may be employed to prepare CDK4 binding peptide. For instance, the peptide, or portions thereof, may be produced by direct peptide synthesis using solid-phase techniques. *In vitro* protein synthesis may be performed using manual  
20 techniques or by automation. Automated synthesis may be accomplished, for example, using an Applied Biosystems Peptide Synthesizer (Foster City, CA) following the manufacturer's instructions. Various portions of the CDK4 binding peptide may be chemically synthesized separately and combined using chemical or enzymatic methods.

25

### Isolation of DNA Encoding the CDK4 Binding Peptide

DNA encoding the CDK4 Binding Peptide may be obtained from a cDNA library. The library can be screened with probes (such as antibodies to the CDK4 binding peptide or oligonucleotides) designed to identify the gene of interest or the  
30 protein encoding by it. Screening the cDNA or genomic library with the selected probe may be conducted using procedures known to those of skill in the art.

### Selection and Transformation of Host Cells

Host cells may be transfected or transformed with expression or cloning vectors described herein for production of the CDK4 binding peptide. The host cells are cultured in conventional nutrient media modified as appropriate for inducing  
5 promoters, selecting transformants, or amplifying the gene encoding the desired sequences. The culture conditions, such as media, temperature, pH and the like, can be selected by skilled artisans without undue experimentation.

Methods of transfection are known to ordinarily skilled artisans, for example, CaPO<sub>4</sub> and electroporation. Alternately, the nucleic acid sequence can be introduced  
10 into viable cells using liposomes, microinjection, cell fusion, DEAE-dextran. Depending on the host cell used, transformation is performed using standard techniques appropriate to such cells.

Suitable host cells for cloning or expressing the DNA in the vectors herein include  
15 prokaryote, yeast, or higher eukaryotic cells. Suitable prokaryotes include, but are not limited to eubacteria, such as Gram-negative or Gram-positive organisms, for example, Enterobacteriaceae such as E. Coli. Eukaryotic cells, including, but not limited to Sf9 cells, 10T1/2 fibroblasts and C2C12 myoblast can also be transfected.

### 20 Vectors

The nucleic acid sequence encoding the CDK4 binding peptide may be inserted into a replicable vector for cloning (amplification of the DNA) or for expression. Various vectors are publicly available. The vector may, for example, be in the form of a plasmid, cosmid, viral particle, phage, or, a baculovirus vector. The  
25 appropriate nucleic acid sequence may be inserted into the vector by a variety of procedures. In general, DNA is inserted into an appropriate restriction endonuclease site(s) using techniques known in the art. Vector components generally include, but are not limited to, one or more of a signal sequence, an origin of replication, one or more marker genes, an enhancer element, a promoter, and a transcription termination  
30 sequence. Construction of suitable vectors containing one or more of these components employs standard ligation techniques which are known to skilled artisans.

The CDK4 binding peptide may be produced recombinantly not only directly, but also as a fusion polypeptide with a heterologous polypeptide, for  
35 example, a nuclear localization signal.



Expression and cloning vectors typically include a selection gene, also termed a selectable marker. Typical selection genes encoding proteins that (a) confer resistance to antibiotics or other toxins, e.g., ampicillin, neomycin, methotrexate, or tetracycline, (b) complement auxotrophic deficiencies, or (c) supply critical nutrients not available from complex media.

Expression and cloning vectors also typically include a promoter operably linked to the nucleic acid sequence which encodes the CDK4 binding peptide. Promoters recognized by a variety of potential host cells are well known, and include inducible and non-inducible promoters.

#### Detecting Gene Amplification/Expression

Gene amplification and/or expression may be measured in a sample directly, for example, by conventional Southern blotting, Northern blotting to quantify the transcription of mRNA, dot blotting (DNA analysis), or *in situ* hybridization using an appropriately labeled probe based on the sequence provided herein. Alternately, gene expression may be measured by immunological methods, such as immunohistochemical staining of cells or tissue sections and assay of cell culture or body fluids, to quantify directly the expression of a gene product. Antibodies useful for immunohistochemical staining and/or assay of sample fluids may be either monoclonal or polyclonal, and may be prepared in any mammal. Conveniently, the antibodies may be prepared against a native sequence of the CDK4 binding peptide or against a synthetic peptide based on the sequences provided herein or against an exogenous sequence fused to the CDK4 binding peptide and encoding a specific antibody epitope.

#### Purification

CDK4 binding peptide may be recovered from culture medium or from host cell lysates, for example, by fractionation on an ion-exchange column; ethanol precipitation; reverse phase HPLC; chromatography on silica or on a cation-exchange resin such as DEAE; chromatofocusing; SDS-PAGE; ammonium sulfate precipitation; gel filtration using, for example, Sephadex G-75; protein A Sepharose columns; and metal chelating columns. Such methods of protein purification are known to those of skill in the art. The purification step selected will depend, for example, on the nature of the production process used.

## Uses

Nucleotide sequences (or their complement) encoding the CDK4 binding peptide have various applications in the art of molecular biology, including uses as hybridization probes, in chromosome and gene mapping and in the generation of anti-sense RNA and DNA. Nucleotide sequences encoding the CDK4 binding peptide are also useful for the preparation of CDK4 binding peptide by the recombinant techniques described herein. The nucleic acid sequences are also useful to generate transgenic animals or "knock out" animals which, in turn, are useful in the development and screening of therapeutically useful reagents. A transgenic animal is an animal having cells that contain a transgene, which transgene was introduced into the animal or an ancestor of the animal at a prenatal, or embryonic, stage. A transgene is a DNA which is integrated into the genome of a cell from which a transgenic animal develops.

The CDK4 binding peptide, as disclosed in the present invention, can be employed therapeutically to inhibit cell proliferation, CDK4 kinase activity or to treat solid tumors, particularly those which over-express CDK4.

The CDK4 binding peptide can be used in *in vivo* or *ex vivo* gene therapy methods. In gene therapy applications, genes are introduced into cells in order to achieve *in vivo* synthesis of a therapeutically effective gene product, for example, the replacement of a defective gene. "Gene therapy" includes both conventional gene therapy where a lasting effect is achieved by a single treatment, and in the administration of gene therapeutic agents, which involves the one time or repeated administration of a therapeutically effective DNA or mRNA. Antisense RNAs and DNAs can be used as therapeutic agents for blocking the expression certain genes *in vivo*.

Methods of transfection are known to ordinarily skilled artisans. The techniques vary depending upon whether the nucleic acid is transferred into cultured cells *in vitro* or *in vivo*, in the cells of the intended host. Examples of suitable techniques for introducing the nucleic acid sequence can be into viable include the use of liposomes, microinjection, cell fusion, DEAE-dextran, calcium phosphate precipitation and electroporation. The currently preferred *in vivo* gene transfer techniques include transfection with viral (typically retroviral) vectors. Depending on the host cell used, transformation is performed using standard techniques appropriate to such cells.

The CDK4 binding peptide and variants thereof may be used therapeutically to inhibit the activity of CDK4 and cell growth or cell division. According to the invention, a composition which includes the peptide of the invention is administered to a cell culture or a patient in need of such treatment wherein the composition  
5 includes an effective amount of the CDK4 binding peptide of the invention. The inhibition of CDK4 activity and/or cell growth has applications in diseases in which CDK4 is over expressed, for example, cancer. In particular, the CDK4 binding peptide can be administered to treat solid tumors which over-express CDK4, such as rhabdomyosarcoma (RMS) and osteosarcoma.

10

#### Pharmaceutical Composition

Another aspect of the invention is directed towards a pharmaceutical composition for inhibiting CDK4 kinase activity, inhibiting cell division, or treating solid tumors which over-express CDK4. The pharmaceutical composition of the  
15 invention includes an effective amount of the CDK4 binding peptide of the invention and a pharmaceutically acceptable excipient or carrier. Suitable pharmaceutical carriers are known by those of skill in the art. Typically, an appropriate amount of a pharmaceutically acceptable salt is used in the formulation to render the formulation isotonic. Examples of the carrier include buffers such as saline, Ringer's solution  
20 and dextrose solution. The pH of the solution is preferably from about 5 to about 8, and more preferably from about 7.4 to about 7.8. Further carriers include sustained release preparations such as semipermeable matrices of solid hydrophobic polymers, which matrices are in the form of shaped articles, e.g., films, liposomes, or microparticles. It will be apparent to those persons skilled in the art that certain  
25 carriers may be more preferable depending upon, for instance, the route of administration and concentration of the CDK4 binding peptide being administered.

#### Delivery

Various methods of administration of peptides are known to those skilled in  
30 the art. Such methods of administration may include, but are not limited to, surface application, oral and parenteral routes, subcutaneous injection, intravenous injection or other pharmaceutical methods of delivery. The peptide can be targeted to specific cells for use in the treatment of cancer. For example, the peptide can be delivered by liposomes, lipophilic tag, injection, viral vectors or fused to a cell specific antibody.  
35 Variants too.

Appropriate dosages of the peptides of the invention will depend upon the condition presented by the individual subject. The dosage administered will vary depending upon factors such as the pharmacodynamic characteristics of the particular agent, and its mode and route of administration: age, health and weight of the recipient; nature and extent of symptoms, kind of concurrent treatment, frequency of treatment, and the effect desired. Effective dosages and schedules for administration may be determined empirically, and making such determinations is within the skill in the art.

#### 10 Anti-CDK4 Binding Peptide Antibodies

The invention further provides anti-CDK4 binding peptide antibodies. Exemplary antibodies include polyclonal, monoclonal, humanized, bispecific and heteroconjugate antibodies.

The anti-CDK4 binding peptide antibodies may include a polyclonal antibody. Method of preparing polyclonal antibodies are known to those skilled in the art. Polyclonal antibodies can be raised in a mammal, for example, by one or more injections of an immunizing agent and, if desired, an adjuvant. Typically, the immunizing agent and/or adjuvant will be injected in the mammal by multiple subcutaneous or intraperitoneal injections. The immunizing agent may include the CDK4 binding peptide, and variants or fusion proteins thereof.

Alternatively, the anti-CDK4 binding peptide antibodies may be monoclonal antibodies. Monoclonal antibodies may be prepared using hybridoma methods which are known to those of skill in the art. In a hybridoma method, a mouse, hamster, or other appropriate host animal is typically immunized with an immunizing agent to elicit lymphocytes that produce or are capable of producing antibodies that will specifically bind to the immunizing agent. The immunizing agent may include the CDK4 binding peptide, and variants or fusion proteins thereof. Alternately, the lymphocytes may be immunized *in vitro*. The lymphocytes are then fused with an immortalized cell line using a suitable fusing agent, such as polyethylene glycol, to form a hybridoma cell. The culture medium in which the hybridoma cells are cultured can then be assayed for the presence of monoclonal antibodies directed against the CDK4 binding peptide, for example, by immunoprecipitation or by an *in vitro* binding assay, such as radioimmunoassay (RIA) or enzyme linked immunoabsorbent assay (ELISA). Such techniques are known in the art.

The antibodies may be monovalent antibodies. Methods for preparing monovalent antibodies are well known in the art. For example, one method involves recombinant expression of immunoglobulin light chain and modified heavy chain. The heavy chain is truncated generally at any point in the Fc region so as to prevent heavy chain crosslinking. Alternatively, the relevant cysteine residues are substituted with another amino acid residue or are deleted to prevent crosslinking. *In vitro* methods are also suitable for preparing monovalent antibodies. Digestion of antibodies to produce fragments thereof, particularly, Fab fragments, can be accomplished using routine techniques known in the art.

10       The anti-CDK4 binding peptide antibodies of the invention may further comprise humanized antibodies or human antibodies. Humanized forms of non-human (e.g., murine) antibodies are chimeric immunoglobulins, immunoglobulin chains or fragments thereof (such as Fv, Fab, Fab', F(ab')<sub>2</sub> or other antigen-binding subsequences of antibodies) which contain minimal sequence derived from non-  
15 human immunoglobulin. Humanized antibodies include human immunoglobulins (recipient antibody) in which residues from a complementary determining region (CDR) of the recipient are replaced by residues from a CDR of a non-human species (donor antibody) such as a mouse, rat or rabbit having the desired specificity, affinity or capacity. In some instances, Fv framework residues of the human  
20 immunoglobulin are replaced by corresponding non-human residues. Humanized antibodies may also comprise residues which are found neither in the recipient antibody nor in the imported CDR or framework sequences. In general, the humanized antibody will comprise substantially all of at least one, and typically two, variable domains, in which all or substantially all of the CDR regions correspond  
25 to those of a non-human immunoglobulin and all or substantially all of the FR regions are those of a human immunoglobulin consensus sequence. The humanized antibody optimally also comprises at least a portion of an immunoglobulin constant region (Fc), typically that of a human immunoglobulin. Methods for humanizing non-human antibodies are well known in the art.

30       Bispecific antibodies are monoclonal, preferably human or humanized, antibodies that have binding specificities for at least two different antigens. Heteroconjugate antibodies are composed of two covalently joined antibodies.

      The anti-CDK4 binding peptide antibodies of the invention have various utilities. The antibodies can be used in diagnostic assays for CDK4 binding peptide,  
35 e.g., detecting its expression in specific cells, tissues serum or tumors. Various

diagnostic assay techniques are known in the art and may be used, such as competitive binding assays, direct or indirect sandwich assays and immunoprecipitation assays conducted in either heterogeneous or homogeneous phases. The antibodies used in the diagnostic assays can be labeled with a detectable moiety capable of producing, either directly or indirectly, a detectable signal. For example, the detectable moiety may be a radioisotope (e.g.,  $^3\text{H}$ ,  $^{14}\text{C}$ ,  $^{32}\text{P}$ ,  $^{35}\text{S}$ , or  $^{125}\text{I}$ ), a fluorescent or chemiluminescent compound (e.g., fluorescein isothiocyanate, rhodamine, or luciferin) or an enzyme (e.g., alkaline phosphatase, beta-galactosidase, or horseradish peroxidase). Any known method for conjugating the antibody to the detectable moiety may be employed.

The antibodies of the invention are also useful for affinity purification of CDK4 binding peptide from recombinant cell culture or natural sources. In this process, the antibodies are immobilized on a suitable support, such as Sephadex resin or filter paper, using methods well known in the art. The immobilized antibody is then contacted with a sample containing CDK4 binding peptide to be purified, and thereafter the support is washed with a suitable solvent that will remove substantially all the material in the sample except the CDK4 binding peptide, which is bound to the immobilized antibody. Finally, the support is washed with another suitable solvent that will release the CDK4 from the antibody. The antibodies also have therapeutic utility.

All references cited in the specification, including in the Working Examples, are hereby incorporated by reference herein.

### **WORKING EXAMPLES**

The following examples are provided to more fully illustrate the principles and practices of the invention. The examples are not intended in any way to limit the scope of the invention.

#### **I. In vitro Examination of MyoD-CDK4 Interaction**

##### **Cloning, Cell Culture and Preparation of Cell Extract**

Using primers with the corresponding restriction sites, chicken MyoD, myogenin, and E12 were cloned into EcoRI/Hind3 digested and CIP-treated pM and pVP16 vectors (Clontech) using standard PCR methods. Sf9 cells were coinfecting with baculoviral stocks encoding CDK4 and cyclin to provide a source of activated CDK4 by methods known to those of skill in the art. After incubation for 48 hours

at 23° C, cell extracts were prepared from the coinfecting Sf9 cells using standard methods in the art.

### Binding Assay

5        The Sf9 cell extract was incubated with agarose bound with either glutathione transferase (GST) alone, or GST fusion proteins encoding one of the four different vertebrate myogenic factors from chicken: CMD1 (MyoD), Ch-myogenin, Ch-myf5 and Ch-mrf4 using methods known to those of skill in the art. Any GST complexes formed were recovered on glutathione-Sepharose beads. The recovered  
10        GST complexes were then washed, heated in sample buffer and loaded on an SDS-PAGE gel.

### Western Blot

15        The gel was then analyzed by immunoblot with anti-CDK4 affinity purified rabbit polyclonal antibody on HyBond ECL (Amersham). The anti-CDK4 antibody was diluted 1:2,000–5,000. The second antibody was HRP anti-rabbit and was diluted 1:10,000 (Pierce cat. no. 31460). The signal was detected using SuperSignal Ultra Reagent (Pierce cat. no. 34075).

20        The results indicate that CDK4 binds specifically to GST-MyoD. Only the GST-MyoD bound CDK4 (data not shown). Binding assays performed with extracts from infected Sf9 cells containing only CDK4 or with bacterially produced CDK4 gave the same results (data not shown). Additionally, the ubiquitously expressed bHLH factors E12 and E47 (proteins that form active heterodimers with MyoD) did not bind CDK4 as GST fusion proteins (data not shown). This  
25        demonstrates that active kinase is not required for CDK4 to bind specifically to MyoD in vitro. Furthermore, the interaction is not mediated by an unknown protein or proteins in the Sf9 cell extracts since purified bacterial proteins give identical results.

## 30        II.        In vivo Determination of MyoD-CDK4 Interaction

Three approaches were used to determine whether or not the observed MyoD-CDK4 interaction occurred in vivo. The combined results from these approaches demonstrate that MyoD and CDK4 interact specifically in vivo.

## A. Coimmunoprecipitation

### Transfection

5        Vectors were prepared essentially as described in Example I. Sf9 cells were coinfecting to produce either MyoD and CDK4 or MyoD and cyclin D1 protein combinations. After incubating the coinfecting Sf9 cells for 48 hours at 23° C, cell extracts were prepared essentially as described in Example 1.

### 10        Coimmunoprecipitation

Coimmunoprecipitation reactions were performed sequentially using the Sf9 cell extracts (adjusted for equal protein concentrations in each reaction), under sequential low (no SDS) and high (with SDS) stringency conditions with the antibody combinations shown in Figure 1 using antibody dilutions of 1:200.

15

### Immunoblotting

Secondary immune complexes were resuspended directly in SDS loading buffer and after SDS-PAGE, proteins were detected by immunoblot essentially as described in Example I, above.

20

### Results

The results are shown in Figure 1: cells coinfecting with baculovirus encoding MyoD and cyclin D1 are in lanes 1 to 3; MyoD and CDK4 are in lanes 4 and 5; and MyoD, CDK4, and cyclin D1 are in lanes 6 to 11. A comparison of lanes 3 and 5 shows that MyoD interacted with CDK4 but not cyclin D1. A comparison of lanes 9 and 11 shows that coexpression of MyoD, CDK4 and cyclin D1 proteins results in MyoD formation of immune complexes containing both CDK4 and cyclin D1. This shows that MyoD binding to the cyclin D1-CDK4 complex does not dissociate the cyclin from the kinase.

30        MyoD expressed in Sf9 cells is phosphorylated on serine residues, as is MyoD expressed in primary cultures of embryonic chick breast muscle. Because MyoD does not readily form homodimers in vitro unless it is dephosphorylated, MyoD is assumed to bind to CDK4 as a monomer in the immunoprecipitation reactions from Sf9 cell extracts.



Coimmunoprecipitation reactions substituting either virally expressed myf5 or myogenin for MyoD failed to produce immune complexes with CDK4, in agreement with in vitro GST fusion-binding results (data not shown).

## 5            **B.     Mammalian Two-Hybrid System**

The interaction between MyoD and CDK4 in vivo was examined using a mammalian version of the yeast two hybrid system described by Finkel et al., (1993) J Biol Chem 268, 5-8.

### 10            Vector Preparation

MyoD and myogenin (MGN) were each cloned into the gal4 DNA-binding domain vector, pM. CDK4 was inserted into the vpl6 activation domain plasmid, pVP16 using methods known to those of skill in the art.

### 15            Transfection

10T1/2 fibroblasts ( $3 \times 10^5$  cells per 60mm dish or multiwell plate) grown in DMEM with either 10% fetal calf serum were co-transfected with either gal4-MyoD or gal4-MGN along with vpl6-CDK4 and a luciferase reporter using Fugene-6 (Boehringer-Mannheim) according to the manufacturer's directions. 1 µg gal4 luciferase reporter, 2 µg each of the gal4 (pM vector, Clonotech) and vpl6 (pvpl6 vector, Clonotech) constructs, and 300 ng of the beta galactosidase reporter pCH110 (Pharmacia), a total of 5.3 µg DNA, were used in each transfection. The pSV2-beta galactosidase reporter was used to normalize transfection efficiencies.

After 24-36 hours, if required, cells were placed in 2% horse serum plus  
25    insulin (10 µg/ml) to induce differentiation and destabilize cyclin D1. 24-48 hrs later cells were harvested for a luciferase reporter assay.

### Luciferase Assay

30    The gal4 luciferase reporter was constructed by exchanging the CAT cassette from pG5 (Clonotech) for the luciferase cassette in pGL3 (Promega). To do so, pG5 was cut with Eco R1 and flush ended with T4 polymerase. The luciferase gene was digested with BamH1/Hind3, flush ended with T4 polymerase and inserted into pG5. The transfection was performed using Fugene-6 (Boehringer-Mannheim) according to the manufacturer's directions.

24–48 hours after transfection, the luciferase reporter assay was performed according to the manufacturer's directions (Promega, cat. no. E4030) and measured in a Victor 1420 Multilabel Counter. The assay was repeated at least three times with similar results. The luciferase reporter assay was normalized for transfection efficiency with a cotransfected beta galactosidase reporter and by total protein in the cell extract with similar results.

### Results

MyoD interactions with CDK4 are shown in lanes 1 to 5 and myogenin interactions with CDK4 are shown in lanes 6–10. Gal4 MyoD–vp16 E12 and Gal4 MGN–vp16 E12 interactions (previously established heterodimer partner combinations) were used as positive controls. See, Figure 2, lanes 1 to 5. Despite the high cellular levels of endogenous CDK4 competing in the two hybrid reaction, a four-fold increase in vp16 CDK4–dependent luciferase reporter activity was routinely detected (an average of three experiments) with the use of the gal4–MyoD construct (Figure 2, lanes 2 and 3) and not with gal4–MGN (Figure 2, lanes 7 and 8).

### **C. Immunoprecipitation**

An immunoprecipitation assay was performed to determine whether MyoD and CDK4 interact in dividing C2C12 myoblasts.

#### Labeling and Preparation of Nuclear Extracts

C2C12 myoblasts were maintained in growth medium and labeled with  $^{35}\text{S}$  (90 minute labeling) using methods known to those of skill in the art. Nuclear extracts were prepared from  $^{35}\text{S}$ –labeled cultures (90 minute labeling) of C2C12 myoblasts maintained in growth medium.

#### Coimmunoprecipitation

Nuclear extracts containing equal counts were sequentially coimmunoprecipitated under sequential low (no SDS) and high (with SDS) stringency conditions with indicated primary and secondary antibody combinations shown in Figure 3 using essentially the same protocol as that described in Example II.

## Results

MyoD-CDK4 immune complexes were identified in dividing myoblasts (Figure 3, lane 6). However, such complexes were not detected in differentiated muscle cultures (data not shown). MyoD and CDK4 interact in dividing C2C12 myoblasts. Lane 6 (Figure 3) shows that anti-MyoD pulls down CDK4 in dividing myoblasts that can be detected with the secondary CDK4 antibody.

### **III. Band Shift Assays**

To ascertain whether or not CDK4 interferes directly with MyoD transactivation functions, the DNA-binding activity of both MyoD homodimers as well as MyoD-E12 heterodimers was measured in band-shift assays using the bacterially expressed and histidine-tag purified proteins, as described by Shirakata et al., *Genes Dev* 7, 2456-70 (1993).

#### Cloning and Transfection

His-tagged CDK4 was cloned as the BamHI/Hind3 fragment in the pRSET plasmid (Invitrogen). Chicken MyoD, myogenin, and E12 were cloned into EcoRI/Hind3 digested and CIP-treated pM and pVP16 vectors (Clontech) using standard PCR methods with primers having the corresponding restriction sites. All constructed clones were checked by sequence analysis on a Perkin-Elmer 310 Genetic Analyzer. His-tagged CDK4 was expressed in the E. Coli strain BL21 as described by Shirakata et al., (1993) *Genes Dev.*, 7:2456-70.

#### Histidine Tag Purification

The protocol for the histidine tag purification technique is identical to Shirakata, *supra*, with slight changes that are not critical to the outcome.

#### Renaturation

The his-tagged CDK4 was renatured through sequential dialysis from urea as described by Kato et al., (1994) *Mol. Cell. Biol.* 14:2713-21.

#### Band Shift Assay

Band shift assays were performed using the bacterially expressed and histidine-tag purified proteins. The MyoD (10 ng), myogenin (10 ng) and E12 (30 ng) proteins from chicken were used with increasing two-fold increments (50-200

ng) of mouse CDK4 protein in the band shift reaction. Limiting amounts of E12 protein were used in the MyoD band shift reactions to observe any CDK4 effects on both the MyoD homodimer as well as the MyoD-E12 heterodimer. DNA binding by a myogenin-E12 heterodimer was used as a control since myogenin does not bind CDK4 in vitro.

### Results

A CDK4 concentration dependent inhibition of DNA binding was observed with the MyoD homo- and heterodimer complexes (Figure 4, lanes 1 to 4). Thus, CDK4 protein inhibited DNA-binding by both the MyoD-E12 heterodimer and the MyoD. No CDK4 inhibition of DNA-binding was observed with the myogenin-E12 complex using the same final level (50–200 ng) of CDK4 protein in the shift reaction (Figure 4, lanes 5 to 8). Thus, DNA-binding by the myogenin-E12 heterodimer and the myogenin homodimer were unaffected at the equivalent concentrations of CDK4 protein in the binding reaction.

Because the actual amount of properly renatured CDK4 protein is unknown, the effective inhibitory ratio of CDK4 to MyoD-E12 complex may be significantly less than five-fold. We assume that CDK4 dissociates the DNA-binding complexes, since no evidence for a supershift was noted either with the addition of CDK4 protein or CDK4 antibody to the shift reactions (data not shown). Most importantly, in agreement with the earlier protein binding studies, CDK4 inhibition of DNA-binding by the MyoD-E12 heterodimer did not depend upon cyclin D1 and, therefore, does not require the active kinase. Thus, CDK4 specifically inhibits MyoD-E12 DNA binding in the absence of cyclin D1.

## **IV. Immunofluorescence**

Immunofluorescence assays were used to determine whether CDK4 was differentially located in nuclei during myogenesis and to determine the effect of interactions between MyoD, cyclin D1 and CDK4.

### Immunofluorescence

To determine whether CDK4 was differentially localized in nuclei during myogenesis, dividing myoblasts in growth medium (GM) as well as differentiated cultures of C2C12 mouse myoblasts in differentiation medium (DM) were reacted with antibodies to CDK4 and cyclin D1 and examined by immunofluorescence.

The antibodies to CDK4 and cyclinD1 were used at 1:200–500 dilution (rabbit or mouse anti-CDK4 and anticyclin D1, Santa Cruz). Second antibody dilutions were also 1:200–500 with either Alexa 488 (green) goat anti-rabbit or mouse, or Alexa 594 (red) goat anti-rabbit or mouse (Molecular Probes).

5

### Results

The results demonstrated that CDK4 is located in the nuclei of dividing myoblasts but translocates to the cytoplasm in differentiated myotubes (data not shown). Furthermore, cyclin D1 is expressed in the nuclei of dividing cells and is completely absent in the nuclei of well differentiated myotubes (data not shown).

10

### **V. Ectopic Expression of Cyclin D1**

To determine whether or not ectopic expression of cyclin D1 could relocalize and maintain CDK4 in myotube nuclei and, thus, in dividing myoblast nuclei, an ecdysone inducible cyclin D1 construct was transiently transfected into C2C12 myoblasts along with an ecdysone inducible beta galactosidase reporter plasmid.

15

Because cyclin D1 is rapidly degraded in the absence of growth factors (the conditions used to differentiate muscle cells), a cyclin D1 protein containing an amino acid substitution that renders it resistant to degradation, mutant T286A, was used in place of the wild-type cyclin D1. Mutant T286A contains an alanine for threonine-286 substitution and is described by Diehl et al., (1997) Genes Dev., 11:957–72.

20

### Cloning

Cyclin D1 was amplified from baculovirus stocks with the appropriate primers and was cloned into the PIND vector (Invitrogen) digested with BamHI/EcoRI.

25

### Transfection

C2C12 cells were transfected with 2 µg each of pIND/cyclin-D1(T286A) and pIND/lacZ (Invitrogen). After 24 hours, the cells were switched to differentiation medium (2% horse serum in DMEM with 10 µg/ml insulin).

30

### Induction

Cyclin D1(T286A) was induced by the addition of 1  $\mu$ M of the ecdysone derivative muristerone. 48 hours later, after well-formed myotubes appeared in the cultures, muristerone was added to a final concentration of 1  $\mu$ M (Invitrogen).

5

### Immunostaining

Cells were fixed 24 hours post induction and immunostained for CDK4, cyclin D1, and lacZ. The first antibodies were used at 1:200–500 dilution (rabbit or mouse anti-CDK4 and anticyclin D1, Santa Cruz; mouse monoclonal anti-lacZ, Gibco BRL). Second antibody dilutions were also 1:200–500 with either Alexa 488 (green) goat anti-rabbit or mouse, or Alexa 594 (red) goat anti-rabbit or mouse (Molecular Probes) for the immunofluorescent reactions.

10

### Results

The results shown induction of both beta galactosidase and stable cyclin D1 (T286A) in well-formed cotransfected myotubes results in the cytoplasmic to nuclear translocalization of endogenous CDK4 (data not shown). There is essentially no detectable cyclin D1 expression in either myotubes or single cells kept in mitogen depleted differentiation medium (data not shown). In contrast, nuclei of rapidly dividing myoblasts maintained in mitogen rich growth medium have high levels of nuclear cyclin D1 (data not shown).

20

This result clearly demonstrates that the nuclear localization of CDK4 in C2C12 myoblasts can be regulated by the cellular level of cyclin D1, which, in turn, is dependent upon the levels of mitogens in the growth medium. Neither the addition of growth medium to control myotubes cultures nor the muristerone induction of a wild-type cyclin D1 construct resulted in the nuclear translocation of CDK4 (data not shown). Thus, the kinase triggering the ubiquitination and degradation of wildtype cyclin D1 is likely active in myotubes, regardless of the growth conditions.

25

30

## **VI. Ectopic Expression of CDK4**

In this example, the affect of ectopically expressed CDK4 on the transactivation functions of MyoD is Examined.

### Plasmid Constructs

Mouse CDK4 was amplified by PCR from baculovirus stocks as outlined in the MaxBac instruction manual (Invitrogen), with primers containing the corresponding restriction sites and was cloned into pVP16 digested with  
 5 BamHI/Hind3.

### Transfection Protocol

10T1/2 fibroblasts ( $3 \times 10^5$  cells per 60mm dish or multiwell plate) grown in DMEM with 10% fetal calf serum (growth medium --conditions which promote the  
 10 nuclear localization of CDK4) were transfected with cotransfected either with an EMSV MyoD or EMSV myogenin expression plasmid, the MCK CAT reporter plasmid, and either an EMSV CDK4 expression construct or the corresponding empty vector using Fugene-6 (Boehringer-Mannheim) according to the manufacturer's directions.

15

### Results

Ectopic expression of CDK4 selectively inhibits MyoD transactivation functions in growth medium and the MyoD myogenic conversion of 10T1/2 cells in differentiation medium in the absence of cyclin D1. CDK4 differentially inhibits  
 20 MyoD (Figure 5, lanes 3 and 4) and myogenin (Figure 5, lanes 7 and 8) activation of the MCK CAT reporter plasmid in 10T1/2 cells grown in differentiation medium (DM). The ectopic expression of CDK4 was able to significantly suppress the MyoD activation of the MCK-CAT reporter (Figure 5, lanes 3 and 4). In contrast, little suppression was observed on the myogenin-dependent activation of MCK-  
 25 CAT (Figure 5, lanes 7 and 8). Thus, CDK4 significantly disrupts the activation functions of MyoD, while having a minimal effect on myogenin reporter activation.

Inhibition of myogenic differentiation by cyclin D1 thus appears to be a consequence of the cyclin D1-dependent nuclear translocation of CDK4 during myogenesis. Furthermore, CDK4 targeted to the myoblast nucleus in the absence of  
 30 cyclin D1 blocks myogenesis.

### **VII. Nuclear Localization of CDK4**

This Example examines whether or not CDK4, in the absence of cyclin D1, can inhibit myogenesis.

35

### CDK4 Expression Construct and Transfection

A CDK4 expression construct with a modified with a five-prime nuclear localization signal (NLS) and a three-prime hemagglutinin tag (HA) was prepared. Cultures of 10T1/2 mouse fibroblasts cells were cotransfected as described in

5 Example VI with a fixed amount of pcDNA-MyoD plasmid (1  $\mu$ g) and increasing amounts of a pcDNA NLSCDK4-HA plasmid (1 to 4 $\mu$ g). Empty pcDNA vector was used as a control and to balance the total plasmid DNA concentration in the transfection. The percentage of myosin positive cells per MyoD positive cell was scored for a minimum of 300 MyoD positive cells for each plasmid concentration.

10 Cultures were maintained in low mitogen differentiation medium to destabilize and eliminate endogenous cyclin D1 and to induce differentiation of the converted cells.

### Results

Forced nuclear expression of CDK4 inhibits myogenic conversion of 10T1/2

15 cells in differentiation medium (DM) in the absence of cyclin D1. Myosin expression in MyoD positive cells was determined as a function of CDK4 plasmid input in the cotransfection. The ratio of myosin positive cells to MyoD positive cells as a function of CDK4 expression plasmid concentration in the transfection was measured. Expression of MyoD and NLSCDK4-HA in the same cell inhibits

20 myogenic conversion (data not shown). MyoD-converted myogenic cells in the absence of NLSCDK4-HA fuse, express MyoD and myosin (data not shown). The forced nuclear localization of CDK4 resulted in an increased number of MyoD-positive single cells that were also negative for myosin expression and fusion as seen in control cells (data not shown). This inhibition, up to 30%, was proportional to the

25 increased expression of CDK4 in the transfected cells (Figure 6). Forced nuclear expression of CDK4 inhibits myogenic conversion of 10T1/2 cells in differentiation medium (DM) in the absence of cyclin D1.

Therefore, the expression of CDK4 targeted to the nucleus, in the absence of cyclin D1 expression, can inhibit MyoD function in a concentration dependent

30 manner, as measured by the reduction in the myogenic conversion of 10T1/2 mouse fibroblasts. From this result we conclude that activated CDK4 is not required to inhibit myogenesis since cyclin D1 is not expressed in cells maintained in differentiation medium. Although cyclin D3 expression is upregulated in differentiated muscle cultures, the cytoplasmic location of CDK4 in myotubes

35 suggests that an active cyclin D3-CDK4 nuclear complex is not formed in low



mitogen medium. Therefore, we assume the forced nuclear localization of CDK4, in the absence of endogenous cyclin D1, does not form an active kinase with cyclin D3.

### VIII. Phosphorylation

5 In this Example, the inventors examined whether an active CDK4 could phosphorylate MyoD directly to inhibit MyoD transactivation functions, by first examining whether or not MyoD could be phosphorylated by CDK4.

#### Production of Activated CDK4

10 Activated CDK4 was prepared from baculovirus infected Sf9 cell extracts essentially as described in Example I.

#### Phosphorylation

An in vitro kinase assay was performed using activated, immunoprecipitated  
15 CDK4 prepared from Sf9 cell extracts. 1–5  $\mu$ l of Sf9 cell extract was mixed with 10  $\mu$ l protein-G slurry (1:1 by volume of protein G suspension) washed with kinase buffer (50 mM Hepes, pH 7.5, 10mM MgCl<sub>2</sub>, 1mM DTT) and 1  $\mu$ l of antibody (Santa Cruz: cat. no. sc-260-G) for one hour on ice. The slurry was then washed three times with 1 ml kinase buffer and then mixed with the 100 ng of either GST-  
20 RB target (pRB, amino acids 769–928, Kato et al., Genes Dev., 1993, 7(3): p. 331–342) or renatured his-tagged MyoD plus or minus 200 ng of GST-pl6 (Serrano et al., Nature, 1993, **336**(6456): p.704–707) incubated in 20  $\mu$ l of kinase buffer and assayed as described by Kato et al., supra.

#### 25 Results

RB phosphorylation was sensitive to the CDK4 inhibitor, pl6 (Figure 7, lanes 1 to 3) whereas MyoD phosphorylation was essentially insensitive to pl6 inhibition (Figure 7, lanes 4 and 5) and was considered CDK4-independent. 2D-peptide maps for MyoD, +/- pl6, using Glu-C and proteinase K reveal no qualitative differences  
30 in the phosphopeptide pattern (data not shown). Phosphorylation inhibited by the addition of pl6 to the kinase reaction, a specific CDK4 inhibitor, was assumed to be the CDK4-dependent component of the phosphorylation reaction.

Of the RB phosphorylation observed, 90–95% was inhibited by pl6 (Figure 7, lanes 2 and 3) whereas only 10–20% of the MyoD phosphorylation was sensitive  
35 to pl6 in the reaction, as determined by phosphoimager analysis (Figure 7, lanes 4

and 5). Two-dimensional phosphopeptide maps of MyoD protein, phosphorylated in the presence and absence of p16 and digested either with Glu-C or proteinase K, also demonstrated no qualitative differences in the phosphopeptide patterns for either enzyme (data not shown). We assume that the non-CDK4-type kinases  
 5 coprecipitated nonspecifically with the CDK4 antibody are responsible for the p16-insensitive MyoD phosphorylation since both p16 and MyoD bound to CDK4 inhibit kinase activity. Our data do not support the hypothesis that cyclin D1 inhibition of myogenesis is associated with a CDK4-dependent phosphorylation of MyoD since CDK4, in the absence of cyclin D1, can block both MyoD DNA-binding and the  
 10 myogenic conversion of 10T1/2 cells, and MyoD is a very poor substrate for CDK4 phosphorylation in vitro compared to RB.

### IX. Mammalian Two-Hybrid System

To determine whether the MyoD-RB reaction is dependent upon the  
 15 expression levels of MyoD in the cell, the mammalian two-hybrid system was used to analyze MyoD, myogenin and RB interactions in vivo in C2C12 muscle cells under growth and differentiation conditions.

#### Vector Preparation

20 Chicken MyoD (CMD1) and myogenin were PCR amplified from pRSET clones (described by Shirakata, et al., Genes Dev., (1993), 7(12A): 2456-70) using Pfu polymerase (Stratagene), a 5' primer containing a BamH1 site and a 3' primer with a Hind3 site, and cloned into the corresponding sites in the vp16 vector pVP16 (Clontech). E2F was cut from CMV-E2F (described by Helin, et al., (1993), Mol  
 25 Cell Biol., 13(10): 6501-8) with BamH1, flush ended with T4 DNA polymerase and cloned into pVP16 that had been cut with MluI and flush ended. Human RB (described by Kaye, et al., (1990), Proc Natl Acad Sci USA, 87(17): 6922-6) was cloned as a flush BamH1/Asp718 fragment into the flush MluI site in the gal4 vector pM (Clontech). Chicken E12 was cloned into the gal4 DNA-binding domain  
 30 vector, pM. The sequence of chicken E12 is unpublished (Paterson lab). However, it is very similar to the human sequence, which is published, and the human sequence could be used in its place. Myogenin (ch-myogenin), (gene bank accession number D90157) was inserted into the vp16 activation domain plasmid, pVP16.

### Cell Culture and Transfection

C2C12 myoblasts ( $3 \times 10^5$  cells per 60 mm dish or multiwell plate) were grown in DMEM with 20% fetal calf serum and transfected with the vectors described above using Eugene-6 (Boehringer Mannheim) according to the  
5 manufacturers directions.

1  $\mu$ g of gal4 luciferase reporter, 2  $\mu$ g each of the gal4 and vp16 constructs, and 300 ng of beta galactosidase expression plasmid, pCH110 (Pharmacia), for a total of 5.3  $\mu$ g DNA, was used for each transfection.

### Cell Harvest and Assay

24–36 hours after transfection, the cells were placed in 2% horse serum plus insulin (10  $\mu$ g/ml) to induce differentiation. After an additional 24–48 hours, cells were harvested for the luciferase reporter assay. Luciferase assays were performed using a Promega kit (cat. no. E4030) following the manufacturer's instructions and  
15 analyzed on a Victor 1420 multi label counter.

### Results

Even in the presence of measurable endogenous levels of RB and E2F, both RB and E2F demonstrated significant interaction in C2C12 cells under growth  
20 conditions (10–15 fold activation of the luciferase reporter). Additionally, these proteins demonstrated significant interaction in low serum medium (used to induce muscle cell differentiation) See Figure 8a, line 7.

In contrast, there was no evidence for any interaction between RB and either MyoD or myogenin (ch-myogenin) in high or low serum culture medium (Figure 8a,  
25 lanes 3 and 5). However, all the control interactions were clearly seen: Both the vp16 MyoD(CMD1) and vp16 myogenin(ch-myogenin) constructs interacted strongly with gal4 E12 (Figure 8b, lanes 4 and 5), a known partner for these myogenic factors. In addition, both the MyoD and myogenin vp16 constructs were capable of efficiently converting 10T1/2 mouse fibroblasts to muscle (data not  
30 shown).

Despite previous reports, these results do not support the hypothesis that either MyoD or myogenin interact with RB to regulate cell cycle decisions in the terminal differentiation of the myoblast. C2C12 cells can differentiate normally under conditions that provide no evidence for an interaction between the myogenic  
35 factors and RB.

## **XI. Mapping the MyoD CDK4 binding domain**

Preliminary results demonstrated that MyoD binds specifically to CDK4 expressed either in baculovirus infected Sf9 cells or in bacteria, either as a  
 5 CDK4/cyclin D1 complex or CDK4 alone (data not shown). Thus, the potential MyoD CDK4-binding domain was mapped.

### Preparation of MyoD-GST fusion proteins

Various domains of MyoD(CMD1), shown in Figure 9 (NH<sub>2</sub>, bHLH and  
 10 COOH fragments) and indicated by amino acid number from chicken MyoD, were amplified by PCR with pPfu with 5' primers containing a BamH1 site and 3' primers with an EcoR1 site and were cloned into the same sites either in pCDNA3 (Invitrogen) or GST-pCEFL (a eukaryotic GST expression vector from S. Gutkind). An NLS (MCPKKRKV) was incorporated into the 5' primer when the amplified  
 15 fragment did not have a nuclear localization signal.

### Fusion Protein Expression

Proteins were expressed in E. coli strain BL21 (DE3) and purified as described by Shirakata et al., Genes Dev. 1993 7(12A):2456-70. The MyoD -GST  
 20 fusion proteins were bound to glutathione agarose.

### Binding Experiments

The binding experiments were performed with CDK4 produced in the baculovirus system (Kato et al., Genes Dev. 1993 7(3):331-42) essentially as  
 25 described by Kaelin et al., Cell 1991 64(3):521-32.

### Deletion mapping

Deletion mapping of the MyoD (CMD1) carboxy terminus narrowed the CDK4-binding region to a maximum of fifteen amino acids between residues 189-  
 30 203, well outside the bHLH domain (Figure 10b, lanes 4 and 5). To confirm that these fifteen amino acids bound CDK4, the fifteen amino acid peptide was joined to glutathione transferase and tested for its ability to bind the CDK4 from Sf9 cell extracts.

## Results

Unexpectedly, CDK4 bound to the carboxy terminus of MyoD (CMD1) in the absence of the bHLH domain (Figure 10a, lane 5). The fifteen amino acid domain in the carboxy terminus of MyoD (CMD1) bound CDK4 as efficiently as full-sized MyoD (CMD1) (Figure 10c, lanes 2 and 3).

## **XII. MyoD inhibition of RB**

To determine whether MyoD could inhibit CDK4 activity towards RB in addition to the ability of CDK4 to influence MyoD function, MyoD(CMD1) was assayed in a CDK4-dependent phosphorylation reaction for its ability to inhibit the phosphorylation of GST-RB in vitro.

### Transfection and Cell culture

Sf9 cells were infected with wild-type virus, cyclin D1 or CDK4 encoding virus stocks. After incubation for 48 hours at 23° C, cell extracts were made using methods known to those of skill in the art.

### Phosphorylation assay

Extracts produced from Sf9 cells coinfecting with virus stocks encoding cyclin D1 and CDK4 were used as a source of activated kinase. Antibody to phosphoserine 780, a CDK4-specific site in RB, was used to measure phosphorylation. Myogenin was used as a control since it does not bind MyoD (Figure 10a, lane 3). Knudsen, et al., *Cell Biol.* (1997),17(10):5771-83; and Kitagawa, et al., *Embo J.* (1996),15(24):7060-9.

## Results

Extracts from Sf9 cells coinfecting with wild-type virus (Figure 11a, lane 1), a cyclin D1 encoding virus (Figure 11a, lane 2) or a CDK4 encoding virus (Figure 11, lane 3) give background levels of kinase activity on serine 780 (antibody to phosphoserine 780). Coinfections with baculovirus stocks encoding CDK4 and cyclin D1 produce active CDK4 (Figure 11a, lane 4) that specifically phosphorylates RB (GST-RB (aa 767-928)) on serine 780. Phosphorylation is inhibited to background levels (e.g., by more than 90%) by the CDK4-specific kinase inhibitor, p16 (Figure 11a, lane 5, added as GST-p16).

### **XIII. Demonstration of CDK4 Binding Peptide Inhibitory Properties**

In this experiment, both the full-sized and the carboxy terminal domain of MyoD (CMD1), were titrated in the CDK4-dependent phosphorylation reaction to test their ability to inhibit kinase activity. Myogenin, which does not bind to CDK4, was used as the control. As before, CDK4-dependent phosphorylation of RB was measured using an antibody to phosphoserine 780.

As used herein, the term "amino terminus of MyoD" refers to amino acids 1–92 of CMD1. The "bHLH domain" refers to amino acids 93–153. The "carboxy terminus" refers to amino acids 153–298. The "fifteen amino acid CDK4-binding peptide" refers to amino acids 189–203. Amino acid 299 is a terminator codon.

#### **Transfection and Cell Culture**

Active CDK4 was produced in Sf9 cells coinfecting with baculovirus stocks encoding CDK4 and cyclin D1 (from C. J. Sherr).

#### **A. CDK4 Kinase Assay**

The kinase assay was performed essentially as described by Kato, et al., *Genes Dev*, (1993), 7(3):331–42. The CDK4-specific kinase inhibitor p16 (from D. Beach, [as described in Serrano, et al., *Nature*, (1993), 366(6456): 704–7]) was used as a GST–p16 fusion added to the kinase reaction. The GST–RB fusion (767–928) was used as a kinase target as previously described Kato, et al., *Genes Dev*, (1993), 7(3):331–42.

To test for kinase inhibition, the various proteins and protein domains were added to the reaction in two-fold increments from 75 ng to 300ng. For the pCDNA3 constructs, total protein concentration was kept constant in the kinase reaction by adding a 6-his tagged amino terminus of MyoD (CMD1) (aa 1–92), which does not bind CDK4. For the GST constructs, total protein concentration was kept constant in the kinase reaction by adding GST protein. After the assay the total reaction was run on SDS PAGE gels and analyzed by Western blot analysis.

Specific phosphorylation of RB was measured with rabbit polyclonal antibodies to RB phosphoserines 780 or 795 (New England Biolabs).

#### **Results**

As shown in Figure 11b, full-length MyoD(CMD1) (second row), the C-terminus of MyoD(CMD1) (third row) and the fifteen amino acid CDK4-binding

peptide fused to GST (fourth row) inhibit the CDK4-dependent phosphorylation of RB(GST-RB) in vitro. Myogenin (first row) (ch-myogenin), which does not bind to CDK4, had no inhibitory effect (Figure 11b, top row). Similarly, neither the N-terminus (amino acids 1-92) nor the bHLH domain of MyoD(CMD1) inhibited

5 CDK4 activity (data not shown). GST protein alone was not inhibitory and behaved similar to myogenin (data not shown). Identical results were obtained using an antibody to phosphoserine 795, another CDK4 dependent phosphorylated residue in RB (data not shown).

Therefore, the observed MyoD-CDK4 interaction in vitro can specifically

10 inhibit the phosphorylation of RB in a dose-dependent manner on serine residues known to be targeted by CDK4. Thus, forced expression of either MyoD or its CDK4-binding subdomain should inhibit CDK4 in cells to block the phosphorylation of RB and arrest growth, similar to the growth inhibitory effects of full-length MyoD.

15

#### B. BrdU incorporation assay

A BrdU incorporation assay was employed to determine whether expression of either the carboxy terminus or the minimal fifteen amino acid CDK4-binding

20 domain of MyoD(CMD1) could induce growth arrest in cultured cells.

#### Transfection & Cell Culture

10T1/2 cells in growth medium were cotransfected with plasmids expressing full-sized MyoD(CMD1) or the indicated domains, either as GST fusions in GST-

25 pCEFL or as subclones in pCDNA3, along with a lacZ expression construct, pCH110, to mark transfected cells. The various domains were targeted to the nucleus with a nuclear tag in the absence of an existing NLS.

#### BrdU assay

30 Cultures were maintained in 20% fetal calf serum. 72 hours after transfection cultures were refed with the same medium and 12 hours later they were given a one hour pulse with BrdU (10 $\mu$ M) prior to fixation, as previously described by Crescenzi et al., PNAS USA 1990 87(21):8442-6; and Sorrentino et al., Nature, 1990 345(6278):813-5. Cells were then reacted with rabbit anti-BrdU antibody

35 (Jackson labs) and Xgal.

## Results

A typical result used in the scoring assay (Sorrentino et al., Nature, 1990, 345(6278): p. 261–72 and Crescenzi et al., Proc. Natl. Acad. Sci. USA, 1990, 87(21): p. 8442–6) to measure the percentage of BrdU positive cells with the transfected cells expressing the various domains of MyoD labeled cells (indicating the cotransfected beta galactosidase expression vector) is shown. All the GST–MyoD domain constructs used were localized to the nuclei of transfected cells, as typified for the fifteen amino acid CDK4–binding peptide fusion with an NLS.

Neither the empty vectors (pCDNA3 or GST–pCEFL with an NLS) nor the amino terminal portion of MyoD(CMD1) (amino acids 1–92 in pCDNA3 with an NLS) were able to inhibit cell growth (Figure 12). In contrast, full MyoD(CMD1) showed growth inhibitory activity (Figure 12).

The amino terminus of MyoD(CMD1) (amino acids 1–92) was ineffective in growth inhibition whereas the bHLH domain (amino acids 93–153) and, to an even greater extent, the carboxy terminus (amino acids 153–298) were both effective at inhibiting cell growth (Figure 12, upper section). Again, the fifteen amino acid CDK4–binding peptide from the carboxy terminus (amino acids 189–203) was as potent as full–sized MyoD(CMD1) in growth inhibitory activity in this assay (Figure 12, lower section). The bHLH domain of MyoD alone also triggered growth arrest, although to a lesser extent.

### C. Phosphorylation of RB

This experiment is designed to confirm that growth arrest correlates with a change in the phosphorylation status of RB induced by MyoD.

### Vector preparation

The inhibitory activity of the fifteen amino acid CDK4 binding peptide on RB phosphorylation in cells was examined by fusing the fifteen amino acid CDK4–binding peptide of MyoD with a nuclear localization tag to the carboxy terminus of GFP and used in the same transfection protocol with GST–RB.



### Transfection and Cell Culture

10T1/2 cells were cotransfected with a GST-RB target (amino acids 767–928) containing a nuclear localization tag, and either MyoD(CMD1) or the carboxy terminus of MyoD with an NLS.

5

### Recovery of GST-RB

48 hours after transfection, nuclear extracts of the 10T1/2 cells were prepared. The nuclear extracts were passed over glutathione agarose to capture the GST-RB target.

10

### Western Blotting

Western blot analysis of the captured GST-RB target was performed with phosphoserine specific antibodies to the CDK4 target sites, serines 780 and 795. Gel loadings for the phosphoserine antibody analysis were adjusted to the same amount of GST-RB target protein by preliminary western analysis of the extracts (Figure 13).

15

### Results

Both the full sized and the carboxy terminal domain of MyoD (CMD1) reduced the phosphorylation of serines 780 and 795 on the cotransfected RB target protein, as shown for the C-terminus with antibodies to phosphoserines 780 and 795 (Figure 13)

20

### D. Growth Inhibition

This experiment was designed to test the inhibitory activity of the fifteen amino acid CDK4-binding peptide on RB phosphorylation in cells.

25

### Transfection

C2C12 myoblasts were cotransfected with a GST-pCEFL RB expression plasmid (RB aa 767–928) and pCDNA3 expression plasmids for full-sized or the C-terminus of MyoD(CMD1). GST-RB was recovered from the cells using methods known to those of skill in the art. The samples were adjusted for equal levels GST protein and loaded on SDS-PAGE gels for western analysis by phosphoserine 780 and 795-specific antibodies.

30

35

Results

The 15 amino acid domain in the carboxy terminus of MyoD that binds CDK4 also inhibits CDK4 kinase activity and cell growth when expressed in cell nuclei.

5           The entire disclosures of all citations cited throughout the specification, and the references cited therein, are hereby expressly incorporated by reference.

          Although the foregoing refers to particular preferred embodiments, it will be understood that the present invention is not so limited. It will occur to those ordinarily skilled in the art that various modifications may be made to the disclosed  
10       embodiments without diverting from the overall concept of the invention. All such modifications are intended to be within the scope of the present invention. Thus only such limitations as appear in the appended claims should be placed upon the scope of the present invention.

15

**WHAT IS CLAIMED IS:**

1. An isolated CDK4 binding peptide comprising:  
Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub>  
wherein Xaa<sub>1</sub>= Cys or Ser; Xaa<sub>2</sub>= Ser or Gly; Xaa<sub>3</sub>= Ser, Ala or Pro; Xaa<sub>4</sub>=Arg or Gln; Xaa<sub>5</sub>= Ser, Cys or Gly; and Xaa<sub>6</sub>=Asp or Glu.
2. The isolated CDK4 binding peptide, wherein the isolated peptide does not include a bHLH domain.
3. A fusion protein comprising:
  - (a) a CDK4 binding peptide comprising Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub> wherein Xaa<sub>1</sub>= Cys or Ser; Xaa<sub>2</sub>= Ser or Gly; Xaa<sub>3</sub>= Ser, Ala or Pro; Xaa<sub>4</sub>=Arg or Gln; Xaa<sub>5</sub>= Ser, Cys or Gly; and Xaa<sub>6</sub>=Asp or Glu; and
  - (b) a heterologous amino acid sequence.
4. The fusion protein of claim 3 wherein the heterologous amino acid sequence comprises a nuclear localization signal.
5. The fusion protein of claim 4 wherein the CDK4 binding peptide is at the C-terminus of the fusion protein.
6. A nucleotide sequence encoding a CDK4 binding peptide, wherein the CDK4 binding peptide comprises:  
Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub>  
wherein Xaa<sub>1</sub>= Cys or Ser; Xaa<sub>2</sub>= Ser or Gly; Xaa<sub>3</sub>= Ser, Ala or Pro; Xaa<sub>4</sub>=Arg or Gln; Xaa<sub>5</sub>= Ser, Cys or Gly; and Xaa<sub>6</sub>=Asp or Glu.
7. The nucleotide sequence of claim 6, wherein the nucleotide sequence is a DNA sequence.
8. A method of inhibiting cell growth, comprising:  
administering to a patient a CDK4 binding peptide comprising:  
Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub>

wherein Xaa<sub>1</sub>= Cys or Ser; Xaa<sub>2</sub>= Ser or Gly; Xaa<sub>3</sub>= Ser, Ala or Pro; Xaa<sub>4</sub>=Arg or Gln; Xaa<sub>5</sub>= Ser, Cys or Gly; and Xaa<sub>6</sub>=Asp or Glu in an amount effective to inhibit cell growth.

9. A method of inhibiting the activity of CDK4 comprising:

contacting CDK4 with a CDK4 binding peptide comprising:

Tyr-Ser-Gly-Pro-Pro-Xaa<sub>1</sub>-Xaa<sub>2</sub>-Xaa<sub>3</sub>-Arg-Arg-Xaa<sub>4</sub>-Asn-Xaa<sub>5</sub>-Tyr-Xaa<sub>6</sub>

wherein Xaa<sub>1</sub>= Cys or Ser; Xaa<sub>2</sub>= Ser or Gly; Xaa<sub>3</sub>= Ser, Ala or Pro; Xaa<sub>4</sub>=Arg or Gln; Xaa<sub>5</sub>= Ser, Cys or Gly; and Xaa<sub>6</sub>=Asp or Glu in an amount effective to inhibit the activity of CDK4.

**ABSTRACT**

The provides a CDK4 binding peptide, and a nucleic acid sequence coding therefore, that is capable of specifically binding cyclin dependent kinase (CDK4) to inhibit CDK4 activity and cell growth. The invention also includes variants of the CDK4 binding peptide which comprise polypeptides which have at least about 80% amino acid sequence identity with the amino acid sequence of the CDK4 binding peptide. In another embodiment, the invention provides chimeric molecules comprising a CDK4 binding peptide fused to a heterologous peptide or amino acid sequence, preferably a nuclear localization signal. Therapeutic and diagnostic methods are also provided.




FIG. 1




FIG. 2





FIG. 3





MyoD	+	+	+	+
E12	+	+	+	+
CDK-4		+	+	+



1 2 3 4

MGN	+	+	+	+
E12	+	+	+	+
CDK-4		+	+	+



5 6 7 8

FIG. 4





FIG. 5




FIG. 6






FIG. 7

**A**



**B**



**FIG. 8**

# GST-CMD




FIG. 9






FIG. 10

**A**

sf-9 Cell Extract  
(64 ng)



**B**



PO4-Rb(Anti-P780)

FIG. 11



CDK-4 Binding	CMD aa		No. BrdU <sup>+</sup> Cells 500 $\beta$ -gal <sup>+</sup> Cells (n=6)	%Inhibition
	Vector		88.4 $\pm$ 6.2	0 %
+	N-CMD	bHLH C-CMD	37.1 $\pm$ 4.2	58 %
-	N-CMD	1-92	86.8 $\pm$ 4.8	2 %
-	bHLH	93-153	58.4 $\pm$ 3.9	34 %
+	C-CMD	153-299	46.9 $\pm$ 6.4	47 %
-	GST	N-CMD	96.7 $\pm$ 5.9	0 %
+	GST	189-203	57.4 $\pm$ 4.3	41 %

FIG. 12




FIG. 13

## SPECIES

## PEPTIDE SEQUENCE

Chicken

YSGPPCSSRRRNSYDS

Human

YSGPPSGARRRNCYEG

Rat

YSGPPSGPRRQNGYDA

Murine

YSGPPSGPRRQNGYDT

Pig

YSGPPSGARRRNCYDG

Consensus

YSGPPC/SG/S-RRR/QN-YD/E-

Xenopus-A

YNSPPCGSRRRNSYD

Xenopus-B

YNSPPCSSRRRNSYD

Zebra fish

FMGPTCQTRRRNSYD

FIG. 14

# PCT

REC'D 21 NOV 2000

WIPO

PCT

## INTERNATIONAL SEARCH REPORT

(PCT Article 18 and Rules 43 and 44)

Applicant's or agent's file reference <b>11613.33W001</b>	<b>FOR FURTHER ACTION</b> see Notification of Transmittal of International Search Report (Form PCT/ISA/220) as well as, where applicable, item 5 below.	
International application No. <b>PCT/US 00/ 14489</b>	International filing date (day/month/year) <b>25/05/2000</b>	(Earliest) Priority Date (day/month/year) <b>18/06/1999</b>
Applicant <b>PATERSON, Bruce M.</b>		

This International Search Report has been prepared by this International Searching Authority and is transmitted to the applicant according to Article 18. A copy is being transmitted to the International Bureau.

This International Search Report consists of a total of 4 sheets.

☒ It is also accompanied by a copy of each prior art document cited in this report.

### 1. Basis of the report

a. With regard to the language, the international search was carried out on the basis of the international application in the language in which it was filed, unless otherwise indicated under this item.

☐ the international search was carried out on the basis of a translation of the international application furnished to this Authority (Rule 23.1(b)).

b. With regard to any nucleotide and/or amino acid sequence disclosed in the international application, the international search was carried out on the basis of the sequence listing :

☐ contained in the international application in written form.

☐ filed together with the international application in computer readable form.

☒ furnished subsequently to this Authority in written form.

☒ furnished subsequently to this Authority in computer readable form.

☒ the statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.

☒ the statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished

2. ☒ Certain claims were found unsearchable (See Box I).

3. ☐ Unity of invention is lacking (see Box II).

4. With regard to the title,

☒ the text is approved as submitted by the applicant.

☐ the text has been established by this Authority to read as follows:

5. With regard to the abstract,

☒ the text is approved as submitted by the applicant.

☐ the text has been established, according to Rule 38.2(b), by this Authority as it appears in Box III. The applicant may, within one month from the date of mailing of this international search report, submit comments to this Authority.

6. The figure of the drawings to be published with the abstract is Figure No.

☐ as suggested by the applicant.

☐ because the applicant failed to suggest a figure.

☐ because this figure better characterizes the invention.

☒

None of the figures.

# INTERNATIONAL SEARCH REPORT

International application No.  
PCT/US 00/14489

## Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☒ Claims Nos.:  
because they relate to subject matter not required to be searched by this Authority, namely:  
  
Although claims 8 and 9 (as far as methods in vivo are concerned) are directed to a method of treatment of the human/animal body, the search has been carried out and based on the alleged effects of the compound/composition.
2. ☐ Claims Nos.:  
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:
3. ☐ Claims Nos.:  
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

## Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this international application, as follows:

1. ☐ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.
2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:
4. ☐ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:

### Remark on Protest

- ☐ The additional search fees were accompanied by the applicant's protest.
- ☐ No protest accompanied the payment of additional search fees.

## INTERNATIONAL SEARCH REPORT

International Application No

P S 00/14489

## A. CLASSIFICATION OF SUBJECT MATTER

IPC 7 C12N15/12 C12N15/62 C07K14/475 C07K7/08 A61K38/10  
A61K38/17 //C07K14/47

According to International Patent Classification (IPC) or to both national classification and IPC

## B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 C12N C07K A61K

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

BIOSIS, EPO-Internal, WPI Data, EMBL

## C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	ZHANG J.M. ET AL.: "Coupling of the cell cycle and myogenesis through the cyclin D1-dependent interaction of MyoD with Cdk4." EMBO J., vol. 18, no. 4, 15 February 1999 (1999-02-15), pages 926-933, XP002151802 the whole document	1,3-9
A	--- -/-	2

☒ Further documents are listed in the continuation of box C.☐ Patent family members are listed in annex.

## \* Special categories of cited documents :

- "A" document defining the general state of the art which is not considered to be of particular relevance
- "E" earlier document but published on or after the international filing date
- "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- "O" document referring to an oral disclosure, use, exhibition or other means
- "P" document published prior to the international filing date but later than the priority date claimed

- "T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention
- "X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone
- "Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.
- "&" document member of the same patent family

Date of the actual completion of the international search

2 November 2000

Date of mailing of the international search report

17. 11. 00

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2  
NL - 2280 HV Rijswijk  
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,  
Fax: (+31-70) 340-3016

Authorized officer

Galli, I

## INTERNATIONAL SEARCH REPORT

International Application No

PCT/US 00/14489

## C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
P,X	<p>ZHANG J.M. ET AL.: "Direct inhibition of G1 cdk kinase activity by MyoD promotes myoblast cell cycle withdrawal and terminal differentiation." EMBO J., vol. 18, no. 24, 15 December 1999 (1999-12-15), pages 6983-6993, XP002151803 the whole document -----</p>	1-9

## PATENT COOPERATION TREATY

PCT

COMMUNICATION OF  
INTERNATIONAL APPLICATIONS

(PCT Article 20)

From the INTERNATIONAL BUREAU

To:

Commissioner  
US Department of Commerce  
United States Patent and Trademark  
Office, PCT  
2011 South Clark Place Room  
CP2/5C24  
Arlington, VA 22202  
ETATS-UNIS D'AMERIQUE  
in its capacity as designated Office

Date of mailing:

28 March 2001 (28.03.01)

The International Bureau transmits herewith copies of the international applications having the following international application numbers and international publication numbers:

International application no.:

PCT/US00/14489

International publication no.:

The International Bureau of WIPO  
34, chemin des Colombettes  
1211 Geneva 20, Switzerland

Facsimile No.: (41-22) 740.14.35

Authorized officer:

J. Zahra

Telephone No.: (41-22) 338.83.38



# PATENT COOPERATION TREATY

## PCT

### INTERNATIONAL PRELIMINARY EXAMINATION REPORT

(PCT Article 36 and Rule 70)

Applicant's or agent's file reference 11613.33WO01	<b>FOR FURTHER ACTION</b> See Notification of Transmittal of International Preliminary Examination Report (Form PCT/IPEA/416)	
International application No. PCT/US00/14489	International filing date (day/month/year) 25/05/2000	Priority date (day/month/year) 18/06/1999
International Patent Classification (IPC) or national classification and IPC C12N15/12		
Applicant PATERSON, Bruce M. et al.		

1. This international preliminary examination report has been prepared by this International Preliminary Examining Authority and is transmitted to the applicant according to Article 36.


2. This REPORT consists of a total of 5 sheets, including this cover sheet.

- ☐ This report is also accompanied by ANNEXES, i.e. sheets of the description, claims and/or drawings which have been amended and are the basis for this report and/or sheets containing rectifications made before this Authority (see Rule 70.16 and Section 607 of the Administrative Instructions under the PCT).

These annexes consist of a total of sheets.

3. This report contains indications relating to the following items:

- I ☒ Basis of the report
- II ☐ Priority
- III ☐ Non-establishment of opinion with regard to novelty, inventive step and industrial applicability
- IV ☐ Lack of unity of invention
- V ☒ Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement
- VI ☐ Certain documents cited
- VII ☐ Certain defects in the international application
- VIII ☒ Certain observations on the international application

Date of submission of the demand  17/01/2001	Date of completion of this report  17.08.2001
Name and mailing address of the international preliminary examining authority:   European Patent Office D-80298 Munich Tel. +49 89 2399 - 0 Tx: 523656 epmu d Fax: +49 89 2399 - 4465	Authorized officer  Halle, F  Telephone No. +49 89 2399 8537



**INTERNATIONAL PRELIMINARY  
EXAMINATION REPORT**

International application No. PCT/US00/14489

**I. Basis of the report**

1. With regard to the **elements** of the international application (*Replacement sheets which have been furnished to the receiving Office in response to an invitation under Article 14 are referred to in this report as "originally filed" and are not annexed to this report since they do not contain amendments (Rules 70.16 and 70.17)*):

**Description, pages:**

1-39 as originally filed

**Claims, No.:**

1-9 as originally filed

**Drawings, No.:**

1-14 as originally filed

**Sequence listing part of the description, pages:**

3, as originally filed

2. With regard to the **language**, all the elements marked above were available or furnished to this Authority in the language in which the international application was filed, unless otherwise indicated under this item.

These elements were available or furnished to this Authority in the following language: , which is:

- ☐ the language of a translation furnished for the purposes of the international search (under Rule 23.1(b)).
- ☐ the language of publication of the international application (under Rule 48.3(b)).
- ☐ the language of a translation furnished for the purposes of international preliminary examination (under Rule 55.2 and/or 55.3).

3. With regard to any **nucleotide and/or amino acid sequence** disclosed in the international application, the international preliminary examination was carried out on the basis of the sequence listing:

- ☐ contained in the international application in written form.
- ☐ filed together with the international application in computer readable form.
- ☒ furnished subsequently to this Authority in written form.
- ☒ furnished subsequently to this Authority in computer readable form.
- ☒ The statement that the subsequently furnished written sequence listing does not go beyond the disclosure in the international application as filed has been furnished.
- ☒ The statement that the information recorded in computer readable form is identical to the written sequence listing has been furnished.

4. The amendments have resulted in the cancellation of:

**INTERNATIONAL PRELIMINARY  
EXAMINATION REPORT**

International application No. PCT/US00/14489

- ☐ the description,      pages:  
☐ the claims,      Nos.:  
☐ the drawings,      sheets:

5. ☐ This report has been established as if (some of) the amendments had not been made, since they have been considered to go beyond the disclosure as filed (Rule 70.2(c)):

*(Any replacement sheet containing such amendments must be referred to under item 1 and annexed to this report.)*

6. Additional observations, if necessary:

**V. Reasoned statement under Article 35(2) with regard to novelty, inventive step or industrial applicability; citations and explanations supporting such statement**

**1. Statement**

Novelty (N)	Yes:	Claims	1-9
	No:	Claims	
Inventive step (IS)	Yes:	Claims	1-9
	No:	Claims	
Industrial applicability (IA)	Yes:	Claims	1-7,9
	No:	Claims	

- 2. Citations and explanations**  
**see separate sheet**

**VIII. Certain observations on the international application**

The following observations on the clarity of the claims, description, and drawings or on the question whether the claims are fully supported by the description, are made:  
**see separate sheet**

**Point V**

1. In this IPER, it is referred to the following document:  
D1: EMBO J. 18, 1999, p. 926-933
- 2.1 The subject-matter of claims 1-9 appears to be novel and to involve an inventive step. Although D1 refers to direct inhibition of G1 cdk (cyclin-dependent kinases) kinase activity by MyoD, an isolated CDK4 as presently claimed is not disclosed therein and cannot be derived therefrom in an obvious way.
- 2.2 The above comments are based on the assumption that all claims enjoy priority rights from the filing date of the priority document. In that case the document cited as P,X-document in the international search report is not considered as prior art.
- 2.3 For the assessment of the present claim 8 on the question whether it is industrially applicable, no unified criteria exist in the PCT Contracting States. The patentability can also be dependent upon the formulation of the claims. The EPO, for example, does not recognize as industrially applicable the subject-matter of claims to the use of a compound in medical treatment, but may allow, however, claims to a known compound for first use in medical treatment and the use of such a compound for the manufacture of a medicament for a new medical treatment.

**Point VIII**

- 3.1 Claim 2 does not meet the requirements of Article 6 and Rule 6.3(a) PCT in that the matter for which protection is sought is not defined in terms of the technical features of the invention. Indeed, the terms "The isolated CDK4 binding peptide" indicate the achieved result without, however, defining the peptide itself. Therefore, claim 2 should for example be rendered dependent on claim 1.
- 3.2 Claim 3 does not meet the requirements of Article 6 PCT in that the matter for which protection is sought is not sufficiently defined and supported by the description. Indeed, the heterologous amino acid sequence in part (b) of said claim is not defined and therefore said amino acid sequence could be any sequence. However, the description does not demonstrate that any sequence

**INTERNATIONAL PRELIMINARY  
EXAMINATION REPORT - SEPARATE SHEET**

---

International application No. PCT/US00/14489

used as a heterologous amino acid sequence would lead to an effective fusion protein.

3.3 Furthermore, the description does not disclose the invention as stated in claim 3 in a manner sufficiently clear and complete for the invention to be carried out by a skilled person (Article 5 PCT). Indeed, as mentioned in the previous item 3.2, the description does not demonstrate that any amino acid sequence could be used in part (b) of said claim in order to obtain an effective CDK4 binding protein. Therefore, the skilled person cannot carry out the invention on the basis of claim 3 as presently defined.

3.4 D1 should be mentioned in the description, cf. Rule 5.1(a)(ii) PCT.

by fax and post

From the  
INTERNATIONAL PRELIMINARY EXAMINING AUTHORITY

PCT

NOTIFICATION OF TRANSMITTAL OF  
THE INTERNATIONAL PRELIMINARY  
EXAMINATION REPORT

(PCT Rule 71.1)

To:

DAIGNAULT, Ronald A.  
MERCHANT & GOULD PC  
P.O. Box 2903  
Minneapolis  
Minnesota 55402-0903  
ETATS-UNIS D'AMERIQUE

FAX: 612-336-4751

Date of mailing  
(day/month/year)

17.08.2001

Applicant's or agent's file reference  
11613.33WO01

## IMPORTANT NOTIFICATION

International application No.  
PCT/US00/14489

International filing date (day/month/year)  
25/05/2000

Priority date (day/month/year)  
18/06/1999

Applicant

PATERSON, Bruce M. et al.

1. The applicant is hereby notified that this International Preliminary Examining Authority transmits herewith the international preliminary examination report and its annexes, if any, established on the international application.
2. A copy of the report and its annexes, if any, is being transmitted to the International Bureau for communication to all the elected Offices.
3. Where required by any of the elected Offices, the International Bureau will prepare an English translation of the report (but not of any annexes) and will transmit such translation to those Offices.

## 4. REMINDER

The applicant must enter the national phase before each elected Office by performing certain acts (filing translations and paying national fees) within 30 months from the priority date (or later in some Offices) (Article 39(1)) (see also the reminder sent by the International Bureau with Form PCT/IB/301).

Where a translation of the international application must be furnished to an elected Office, that translation must contain a translation of any annexes to the international preliminary examination report. It is the applicant's responsibility to prepare and furnish such translation directly to each elected Office concerned.

For further details on the applicable time limits and requirements of the elected Offices, see Volume II of the PCT Applicant's Guide.

Name and mailing address of the IPEA/

 European Patent Office  
D-80298 Munich  
Tel. +49 89 2399 - 0 Tx: 523656 epmu d  
Fax: +49 89 2399 - 4465

Authorized officer

Büchler, S

Tel. +49 89 2399-8090

